

Assessing the technical aspects of OAE approaches

Matthew D. Eisaman^{1*}, Sonja Geilert^{2*}, Phil Renforth^{3*}, Laura Bastianini³, James Campbell³, Andrew W. Dale⁴, Spyros Foteinis³, Patricia Grasse^{4,5}, Olivia Hawrot³, Carolin R. Löscher⁶, Greg H. Rau^{7,8}, Jakob Rønning⁶

5 ¹ Department of Earth & Planetary Sciences and [the Yale Center for Natural Carbon Capture](#), Yale University, New Haven, CT, USA

² Department of Earth Sciences, Utrecht University, Utrecht, The Netherlands

³ Research Centre for Carbon Solutions, Heriot-Watt University, Edinburgh, EH14 4AS, United Kingdom

⁴ GEOMAR Helmholtz Centre for Ocean Research Kiel, 24148, Kiel, Germany

10 ⁵ German Centre for Integrative Biodiversity Research (iDiv) Halle-Jena-Leipzig, 04103, Leipzig, Germany

⁶ Danish Institute for Advanced Study (DIAS)/Nordcee, University of Southern Denmark, Odense, Denmark

⁷ Planetary Technologies, Inc., Dartmouth, NS, Canada

⁸ Institute of Marine Sciences, University of California, Santa Cruz, CA, USA

15 *Correspondence to:* Matthew D. Eisaman (matthew.eisaman@yale.edu), Sonja Geilert (s.geilert@uu.nl), Phil Renforth (p.renforth@hw.ac.uk)

Abstract

Ocean alkalinity enhancement (OAE) is an emerging strategy that aims to mitigate climate change by increasing the alkalinity of seawater. This approach involves increasing the alkalinity of the ocean to enhance its capacity to absorb and store carbon dioxide (CO₂) from the atmosphere. This chapter presents an overview of the technical aspects associated with the full range of OAE methods being pursued and discusses implications for undertaking research on these approaches. Various methods have been developed to implement OAE, including: the direct injection of alkaline liquid into the surface ocean, dispersal of alkaline particles from ships, platforms or pipes, the addition of minerals to coastal environments, ~~or~~ and the electrochemical removal of acid from seawater. Each method has its advantages and challenges, such as scalability, cost-effectiveness, and potential environmental impacts. The choice of technique may depend on factors such as regional oceanographic conditions, alkalinity source availability, and engineering feasibility. This chapter considers electrochemical methods, the accelerated weathering of limestone, ocean liming, the creation of hydrated carbonates, and the addition of minerals to coastal environments. In each case, the technical aspects of the technologies are considered and implications for best-practice research are drawn. The environmental and social impacts of OAE will likely depend on the specific technology and the local context in which it is deployed. Therefore, it is essential that the technical feasibility of OAE is undertaken in parallel with, and informed by, wider impact assessments. While OAE shows promise as a potential climate change mitigation strategy, it is essential to acknowledge its limitations and uncertainties. Further research and development are needed to understand the long-term effects, optimize techniques, and address potential unintended consequences. OAE should be viewed as complementary to extensive emission reductions, and its feasibility may be improved if it is operated using energy and supply chains with minimal CO₂ emissions.

20
25
30

Formatted: Superscript

35 3.1 Introduction

3.1.1 Overview of Ocean Alkalinity Enhancement approaches

The oceans could be artificially alkalized by the addition of alkali (sodium, Na, or potassium, K) and alkaline (magnesium, Mg, or calcium, Ca) silicates, carbonates, oxides, and hydroxides, often as solids, but also in dissolved, aqueous form. The suite of technologies that aim to achieve this is referred to as ocean alkalinity enhancement (OAE). Figure 1 provides a comparative overview of some of the most widely considered OAE approaches.




Figure 1: Categorization of different OAE approaches by alkalinity source, processing method, alkalinity type, and dispersal location. Each pathway colour represents a unique approach. Dispersal location options are determined by alkalinity type. Liquid alkalinity will likely be dispersed on the coast due to its relatively low value of alkalinity per unit volume and mass, whereas solid alkalinity could be dispersed nearshore, offshore, or directly on the seafloor (in shallow water <100 m depth).

Approximately 0.25 Gt yr^{-1} of carbon is removed from the atmosphere due to weathering of silicate rocks on land (Hartmann et al., 2009). The products of this natural process (e.g., Na^+ , K^+ , Mg^{2+} , Ca^{2+} , HCO_3^- , CO_3^{2-} , H_4SiO_4 , etc.) are transferred, via rivers and groundwaters, to the ocean where they can durably reside for thousands of years (Renforth and Campbell, 2021). This natural process can be enhanced by first mining and grinding the Mg- and Ca-rich silicate rocks such as basalt and peridotite into fine powders and adding them to the ocean (Rigopoulos et al., 2018; Köhler et al., 2013). However, for full dissolution of silicate minerals in the ocean surface, very small particles are needed ($<10 \mu\text{m}$), and as such, the grinding energy to achieve this can be prohibitive (Hangx and Spiers, 2009; Strefer et al., 2018). Instead, larger grains ($<100 \mu\text{m}$) can be applied to coastal zones (Montserrat et al., 2017) where waves and tides have been suggested to help break down the particles and accelerate dissolution in seawater in close contact with the atmosphere in a process known as coastal enhanced weathering (CEW) (Chapter 3.6 and 3.7). Although these larger particles dissolve more slowly, they have a lower initial environmental footprint and could be integrated into coastal management schemes such as beach nourishment (Foteinis et al., 2023).

Carbonate rocks, such as limestone (CaCO_3) and dolomite ($\text{CaMg}(\text{CO}_3)_2$), are sometimes proposed as an alternative to silicate rocks for OAE due to their faster dissolution in water. However, the surface ocean waters are almost everywhere supersaturated with respect to calcite and aragonite (Orr et al., 2005), implying that limestone is unlikely to dissolve. One solution is to allow

the CaCO₃ to sink to deeper water where it is undersaturated (Harvey et al., 2008), but the significant delay in making contact with the atmosphere and technical challenges limit this approach. Another solution is to convert the limestone to a more soluble form (i.e., calcium bicarbonate: Ca(HCO₃)_{2(aq)}) by first dissolving it in a reactor with high [partial pressure of CO₂ \(pCO₂\)](#) (Rau & Caldeira, 1999). This approach is termed accelerated weathering of limestone (AWL) (Chapter 3.3). Potential improvements to AWL include systems such as buffered AWL, whereby [alkaline minerals hydrated lime](#) (e.g., [hydrated lime](#) Ca(OH)₂) is added to buffer the unreacted CO₂ before being discharged to seawater (Caserini et al., 2021). Calcium bicarbonate solutions for OAE may also be produced electrochemically (Rau, 2008). For these approaches to be meaningful for CDR, the concentrated CO₂ used in the process must come from the atmosphere ([or the surface ocean](#)), via direct air capture (DAC) or from biomass combustion or metabolism.

65

70 Alternatively, limestone could be used to create more reactive materials such as lime (CaO) or Ca(OH)₂, which dissolve rapidly in the ocean surface – a process referred to as ocean liming (OL) (Khesghi, 1995) (Chapter 3.4). Other fast-dissolving solids have been suggested as liming agents including brucite (Mg(OH)₂) (Renforth and Kruger, 2013) and sodium carbonate ('soda ash', Na₂CO₃) (Khesghi, 1995). However, CaO could be mass-produced by the mining, grinding and then calcining of limestone, potentially using the pre-existing spare capacity of the cement industry (Renforth et al., 2013). The CO₂ produced in the calcination step can be stored geologically or even utilized and the CaO, or most likely the Ca(OH)₂, transported and spread to the oceans. Nevertheless, open questions remain, particularly around the effect of localized pH increase on the marine ecosystems in the wake of the delivery vessels (Caserini et al., 2021; He and Tyka, 2023), or pipes, while the potential runaway CaCO₃ precipitation could lower the CO₂ sequestration efficiency of the approach (Moras et al., 2022).

75

80 Alternative pathways are being explored to cost-effectively hydrate minerals and use them as reactive alkaline feedstocks (Chapter 3.5). Ikaite is one example of a hydrated calcium carbonate mineral which is not supersaturated in the ocean, making it potentially viable for OAE (Renforth et al., 2022). In general, hydration of carbonates has the potential to be less energy intensive than calcination of limestone, while offering comparable alkalinity enhancement to lime and slaked lime.

85

90 Aqueous salt solutions such as seawater and brines (e.g., desalination wastes, and geological fluids) could potentially provide an abundant source of alkalinity through their electrochemical processing to produce aqueous NaOH_(aq) or other hydroxides, which can be used for near-instant OAE and CO₂ drawdown (Chapter 3.2). There are two main methods of electrochemically generating alkalinity from aqueous salt solutions: electrolysis and electrodialysis. Electrolysis (Willauer et al., 2014) produces high-concentration (approx. 26 wt.%) NaOH_(aq), along with significant quantities of H_{2(g)} and Cl_{2(g)} which must be used within existing energy or product markets or safely stored through reaction with silicate rocks. Electrodialysis, (Eisaman et al., 2012) produces lower concentration NaOH_(aq) (approx. 4 wt.%) along with HCl_(aq) and negligible amounts of H_{2(g)} and O_{2(g)} that are vented. Electrodialysis has a lower theoretical voltage drop than electrolysis per mole of alkalinity generated because it relies on enhancing water dissociation and the subsequent separation of H⁺ and OH⁻ ions across ion exchange membranes, while

Formatted: Subscript

Formatted: Not Superscript/ Subscript

95 electrolysis employs the splitting of water at an electrode surface (Kumar, Du, and Lienhard, 2021). That said, electrodialysis produces lower concentrations of $\text{NaOH}_{(\text{aq})}$ than electrolysis. In electrolysis $\text{H}_{2(\text{g})}$ can be burned for energy, or utilized, but the $\text{Cl}_{2(\text{g})}$ can be difficult to dispose of and is a potential environmental hazard. In electrodialysis, a use or neutralization pathway must be found for the dilute $\text{HCl}_{(\text{aq})}$, for example, by neutralization upon contact with abundant sources of mineral alkalinity.

100 Even though OAE approaches have the potential to remove atmospheric CO_2 at the Gt yr^{-1} scale, they are also responsible for carbon and other emissions during their life cycle. For example, nitrogen-containing explosives (Tovex) that are typically used for mining which can impact eutrophication (Foteinis et al., 2022), whereas nickel (Ni) releases from olivine dissolution could contribute to aquatic toxicity (Foteinis et al., 2023), although low solubility or co-precipitation with secondary minerals may limit the impact (Guo et al., 2022). Therefore, for sustainable and scalable OAE the life cycle environmental impacts of each
105 approach should be considered and accounted for via life cycle assessment (LCA), rather than simply relying on carbon balances alone. By doing so, not only is the net carbon dioxide equivalent ($\text{CO}_{2\text{eq}}$) removal quantified but avoided emissions and tradeoffs with other environmental impacts are also identified. For consistent and meaningful LCAs for OAE, standardized guidelines are required, since the relevant ISO standards (ISO 14040 and 14044) only provide generic guidance that is not technology/sector specific. For this reason, the LCA should be specially tailored to OAE applications. Previous work on LCA
110 best practices for similar sectors, such as those for DACS (Cooney et al., 2022) and for the wider CDR sector (Terlouw et al., 2021) can serve as a useful starting point.

3.1.2 OAE Technology Readiness Level

Technology readiness levels (TRLs), developed by NASA in the 1970s, are an estimate of technological maturity. TRLs are based on a scale from 1 to 9, with 9 being the most mature technology (Heder, 2017). Research institutes tend to focus on
115 TRLs 1 to 4, while the private sector focuses on TRLs 7 to 9. Several OAE approaches lie between TRLs 4 to 7, sometimes called the ‘Valley of Death’, where neither research institutes nor the private sector prioritize investment.




Figure 2. Technology Readiness Levels (TRLs) for different Ocean Alkalinity Enhancement approaches: 1. Basic principles observed; 2. Technology concept formulated; 3. Experimental proof of concept; 4. Technology validated in laboratory environment; 5. Technology validated in a relevant environment; 6. Technology demonstrated in a relevant environment; 7. System prototype demonstration in an operational environment; 8. Actual system completed and qualified; 9. Actual system proven in an operational environment.

The TRL of OAE approaches is summarized in Fig. 2. A feasibility case study for an AWL system attached to a coastal power plant in Taiwan (Chou et al. 2015), and most recently a pilot scale AWL reactor for flue gas separation (Kirchner et al., 2020), suggests TRL 5 - 6. Electrochemical brine splitting has a similar TRL of around 6 with several start-up companies in the process of deploying pilot demonstrations. CEW has a lower TRL of between 4 to 5, currently undergoing field trials in Southampton, New York to prove its efficacy. There are still significant challenges to scaling up the approach, particularly surrounding monitoring reporting and verification (e.g., Burt et al., 2023, see Ho et al., 2023, this Guide), potential ecosystem effects (Bach et al., 2019), as well as logistical challenges around mining, grinding, and transporting enough alkaline material from land to distribute in the marine environment which would require massive infrastructure and long supply chains (Renforth et al., 2013). Previously, OL has been assigned a TRL of 3 to 4 (McLaren, 2012), but can now be considered to have advanced to a TRL of 4 to 5 after recent field trials in Florida. Finally, the production and application of hydrated carbonate minerals such as ikaite has a TRL of 1 (Renforth et al., 2023), currently under investigation at the bench-scale at Heriot-Watt university examining aspects such as air stability and seawater dissolution kinetics.

135 Overall, while OAE may have great potential for CDR, there are still many unanswered questions about the long-term
ecological impacts and the feasibility of implementing these techniques on a large scale. As such, further research and
development is needed to increase the TRLs of these approaches and which, if any, other approaches should be scaled up. The
ocean is a heterogeneous system and field-tests are required across a variety of oceanic conditions, e.g., temperatures,
upwelling velocities, seawater chemistries, and biological profiles. A research program designed to accelerate technology
140 development and demonstration of pilot-scale facilities will also need to assess any potential ecological impacts and
governance issues.

3.2 Electrochemical production of alkalinity for OAE

3.2.1 Technical Summary - chloride brines

Aqueous brine (for example, $\text{NaCl}_{(\text{aq})}$) represents an abundant source from which aqueous alkalinity (for example $\text{NaOH}_{(\text{aq})}$)
145 can be generated using electrochemistry. In these approaches, the alkalinity is in the form of hydroxide ions ultimately derived
from the water in the brine stream, with the dissolved brine ions (for example Na^+ and Cl^-) providing the conductivity and
charge balance needed for the process.

The two primary electrochemical processes used to generate alkalinity from brine are electrolysis (O'Brien, Bommaraju, and
150 Hine, 2005, pp.31-34) and electrodesialysis (Strathmann, 2011, pp.163-167), as shown in Fig. 3. Electrolysis generates higher
concentration alkalinity than electrodesialysis but requires a higher electrical potential per mol of alkalinity to do so.




Figure 3. Process flow for the electrochemical conversion of aqueous chloride brine into alkalinity. Both pretreatment and the separation of brine into divalent rich and divalent lean streams is optional and is not performed in all processes.

155 This is because electrolysis uses more energy-intensive *water splitting* at electrodes to generate the alkalinity, while electrodesialysis uses *enhanced water dissociation* at the junction of the bipolar membranes, combined with ion-selective

separation. While the primary by-products from electrolytic alkalinity generation are Cl_2 and H_2 gasses, the primary by-product from electrolysytic alkalinity generation is aqueous acid, for example $\text{HCl}_{(\text{aq})}$.

160 The electrolytic generation of alkalinity from an NaCl solution (see Fig. 4) is essentially the well-known chlor-alkali process (O'Brien, Bommaraju, and Hine, 2005, pp. 31-34), where aqueous brine (approx. 26 wt%) and NaOH (approx. 28 wt%) are converted into less concentrated brine (approx. 24 wt%), more concentrated NaOH (approx. 30 wt%), hydrogen gas (H_2), and chlorine gas (Cl_2) (Kumar, Du, and Lienhard, 2021). The development of efficient and durable oxygen selective electrodes is critical to making seawater electrolysis more feasible (La Plante et al., 2023).

165





Figure 4. Typical process flow for the electrolytic conversion of aqueous NaCl -rich brine into alkalinity using the chlor-alkali membrane process. A chlor-alkali diaphragm process also exists but is not shown (Kumar, Du, and Lienhard, 2021).

The electrolysytic generation of alkalinity from an NaCl brine typically uses three-chamber bipolar membrane electrolysysis (BPME) (Strathmann 2011, pp.163-167, Fig. 5). In this process, aqueous brine (approx. 3.5-5 wt%), HCl (approx. 2 wt%), and NaOH (approx. 2 wt%) are converted into less concentrated brine (approx. 2-3.5 wt%), more concentrated HCl (approx. 3-4 wt%), and more concentrated NaOH (approx. 3-4 wt%). Hydrogen gas (H_2) and Oxygen gas (O_2) are created at the end electrodes, but in contrast to electrolysis, because there are typically 50 - 200 membrane triplets between each pair of electrodes, the rate of H_2 and O_2 gas generation relative to the rate of NaOH production is negligible, reduced by a factor of (number of cell triplets)⁻¹ relative to electrolysis. In practice the H_2 and O_2 gasses generated during electrolysysis are combined and vented. The $\text{HCl}_{(\text{aq})}$ generated in this process is used on land in processes that result in the neutralization of the acid, for example in the neutralization of alkaline waste ponds found at sand and gravel operations. Scaling to $\text{Gt CO}_2 \text{ y}^{-1}$ will require larger-scale uses of the acid such as the pre-treatment of silicate rocks to enhance the kinetics and capacity of CO_2 mineralization (Guy and Schott, 1989; Pollyea et al. 2017).



180


Figure 5. Typical process flow for the electrodialytic conversion of aqueous brine into alkalinity.

Once the alkalinity is generated, it must be dispersed into the ocean. An advantage of aqueous hydroxides such as $\text{NaOH}_{(\text{aq})}$ is that the rate at which the alkalinity source is *added* to the ocean is equal to the rate at which alkalinity is actually *delivered* to the ocean. In contrast, with solid forms of alkalinity such as crushed minerals, the relationship between rate of alkalinity source *added* and the rate at which this potential alkalinity is *delivered* to the ocean depends on the dissolution kinetics of the solid. From a molecular point of view, since the Na^+ and OH^- ions came from the seawater itself, the net effect of the process is simply the removal of acid in the form of H^+ and Cl^- ions.

185


Once the alkalinity has been delivered to the ocean, the response of the ocean and atmosphere is governed by two timescales: an immediate timescale that corresponds to the response of the carbonate chemistry of the ocean (Reaction 1):

190




and a slower timescale of weeks to months that corresponds the re-equilibration of CO_2 in the air and surface ocean via air-sea gas exchange (Reaction 2):

195



The net reaction described by Reactions (1) and (2) once equilibrium has been reached is (Reaction 3):



where coefficients $a - e$ are molar ratios relative to the added OH^- (added alkalinity), $a = b + c$ (carbon mass balance) and $b + 2c + d = 1$ (charge balance). For example, modelling in CO₂SYS (citation) shows $a = 0.827$, $b = 0.742$, $c = 0.086$, $d = 0.086$, $e = 0.095$ in seawater at an equilibrium pH of 8.1, $S = 35$ ppt, $T = 20$ °C and $P = 1$ bar. These ratios are sensitive to the preceding seawater variables; previously reported values for the ratio of moles of removed CO₂ to moles of added alkalinity (a coefficients) range from 0.75 to more than 0.85 (Tyka et al. 2022; He and Tyka 2023; Renforth and Henderson 2017; Wang et al. 2023).

As shown in Reaction (R1), on fast timescales, the addition of alkalinity decreases the dissolved CO₂ concentration, putting the surface ocean pCO₂ out of equilibrium with atmospheric pCO₂. On slower timescales of weeks to months for Reaction (R2), equilibrium is re-established as CO₂ from the atmosphere replenishes the CO₂ deficit in the surface ocean. The combined result of these two processes is the net removal of CO₂ from the atmosphere and storage as oceanic bicarbonate and carbonate ions.

Upon dispersal to the ocean, the added alkalinity is increasingly diluted as it moves away from the point of addition. This results in a mixing zone centred at the point of alkalinity addition where the increase in pH and total alkalinity (TA) is largest. The ratio of the rate of alkalinity addition to the rate of dilution must be kept sufficiently low to avoid the precipitation of Mg(OH)₂ (which can result in an undesired increase in turbidity) or CaCO₃ (which reduces the efficiency of OAE for CO₂ removal) within the mixing zone (Hartmann et al. 2023). Due to this constraint and the permitted limits in the mixing zone for parameters such as pH and turbidity, in practice the pH of aqueous alkalinity may need to be reduced prior to dispersal. For example, prior to release into the ocean, the alkalinity could be mixed with the partially desalted brine stream from which the alkalinity was generated.

To reduce the need for dilution, the alkalinity may first be contacted with CO₂ in air to decrease the pH by converting some of the hydroxide (OH⁻) into carbonate (CO₃²⁻) (Stolaroff et al. 2008). This has the added advantage that all the CO₂ captured in this way is measurable and verifiable through direct measurement. This effectively provides a tuneable knob to perform “partial direct air capture (DAC)” to the degree required to reach the target pH, at which point it can be diluted to the pH required by permitting, and the remainder of the CO₂ removal can occur via OAE once it is dispersed into the ocean. The advantage of this use of DAC as a “partial pre-equilibration” for OAE compared to standard DAC, is that when used as a preparation step for OAE, no energy needs to be applied to release the CO₂ as a pure gas. As an example, if one generates approximately 4% NaOH_(aq) using electro dialysis, partial DAC can be used to bring the pH into the range 11 - 12, at which point it can be blended with waste brine to the final pH suitable for ocean delivery.

Rather than partial DAC and dilution, aqueous alkalinity may be directly delivered to the ocean at higher concentrations as long as natural or engineered dilution rates in the mixing zone avoid unwanted precipitation and stay within permitted bounds.

235 Alternatively, when discharged within permitted turbidity limits, more slowly dissolving forms of particulate alkalinity such as $\text{Mg}(\text{OH})_2$ could be used to distribute the added alkalinity more evenly in space and time (Fakhraee, et al., 2023).

A process that is very related to OAE using chloride brines is “indirect ocean capture” or IOC (de Lannoy et al. 2018; Eisaman et al. 2018; Eisaman et al. 2020), also referred to as “direct ocean capture”, “direct ocean removal” (DOR), or “CO₂ removal from ocean water” (Kim et al., 2023). This approach employs *alkalinity cycling* to remove CO₂ from the ocean, but *without a net increase in ocean alkalinity* or DIC. Because the net alkalinity is not enhanced in this process, it should not be labelled as

245 OAE. In one version of this approach, electrodialysis is first used to generate $\text{HCl}_{(\text{aq})}$ and $\text{NaOH}_{(\text{aq})}$ from brine streams containing $\text{NaCl}_{(\text{aq})}$. The acid is used to acidify seawater, decreasing its pH and alkalinity, and shifting all its DIC to dissolved CO₂ gas, which is then vacuum stripped out of the seawater (de Lannoy et al. 2018; Eisaman et al. 2018). The alkaline base is then added to the now decarbonized seawater to restore its lost alkalinity, resulting in CO₂ moving from the air to the seawater to restore equilibrium, thereby replacing the vacuum-stripped CO₂. At a high level, this approach uses the ocean as a pump, in contrast to OAE, which uses the ocean as a sponge. In a second version of this approach, the $\text{NaOH}_{(\text{aq})}$ is added to seawater to remove CO₂ as $\text{CaCO}_{3(\text{s})}$, with additional $\text{NaOH}_{(\text{aq})}$ then added to restore this lost alkalinity and draw CO₂ from the air to replace the removed CO₂ (de Lannoy et al. 2018; Eisaman et al. 2018). The precipitation of $\text{CaCO}_{3(\text{s})}$ [reduces alkalinity](#)

250 [\(resulting in either in lower efficiency of CO₂ removal per unit of added alkalinity in the case of OAE, or a releases of CO₂ in cases where the precipitation occurs in the absence of an alkalinity addition\)](#), making this second version relatively inefficient from a CO₂-removal perspective, but may be pursued if other considerations such as ease of verification outweigh this inefficiency. A third version of this approach relies primarily on the precipitation of $\text{Mg}(\text{OH})_2$, in addition to the precipitation of some CaCO_3 , and prevents release of CO₂ in the process of CaCO_3 precipitation by generating alkalinity at a sufficiently high rate to keep the pH at a constant target value (La Plante et al. 2021; La Plante et al., 2023).

Formatted: Subscript

3.2.2 Technical Summary - non-chloride brines and minerals

260 In addition to the production of alkalinity from chloride salts discussed above, hydroxides can also be electrochemically produced from non-chloride salt solutions such as Na, K, Ca or Mg sulphates, nitrates or carbonates. One disadvantage of such an approach is that such salts are much less naturally abundant or less soluble than chloride salts, though they can be present in waste streams. However, as will be described, they can be produced from mineral sources of metal cations and recycled anions. Because of electrochemical issues with nitrate salts and because carbonate salts present more limited net carbonation potential and often have less solubility, the focus here will be on metal sulphate salts.





Figure 6. Example of a non-chloride metal salt used to electrochemically produce an acid, a metal hydroxide, and in the case of electrolysis, H₂ and O₂.

As in the case of NaCl-Na₂SO₄ such solutions can be electrolyzed or electro-dialyzed to produce, in this case, H₂SO₄ (sulfuric acid) generated/concentrated at the anode and NaOH at the cathode (Little et al. 2012). In electrolysis, H₂ and O₂ (rather than Cl₂) are also produced at the cathode and anode, respectively (Fig. 6).

While the NaOH can be used for OAE CDR as described above, uses of the acid at the production scales required for globally significant OAE must be identified. Such acids (including the hydrochloric acid described in the previous section) can be reacted with alkaline minerals to produce more neutral metal salts and water (La Plante et al., 2023). For example, the reaction of sulfuric acid with the silicate mineral forsterite (Mg₂SiO₄) yields MgSO₄, SiO₂ and H₂O (Reaction 4):



As suggested by House et al. (2007) such metal salts produced from the preceding reaction are in theory benign and could be added to the ocean. However, most silicate minerals contain multiple metals that upon acidification yield metal salts such as Mg, Ca, Fe, Ni, Co and Na sulphates or chlorides in solution. While at least some of these metal salts will have limited solubility in alkaline seawater, their disposal in the ocean would be problematic due to potential biological effects (see Chapter 4). One alternative is to take advantage of the differences in the reduction in metal solubility as pH rises to selectively remove the less soluble metals as solid metal hydroxides, such as Fe(OH)₂, Ni(OH)₂ and Co(OH)₂, as is commonly done in metal extraction from rocks (Hamilton et al. 2020). Some of the produced NaOH could be used to facilitate pH elevation of the metal salt solution and the resulting valuable metal precipitates can be harvested for further refining. The remaining, more soluble metal salts, e.g., MgSO₄, CaSO₄ and Na₂SO₄, could then provide a more benign way to dispose of the products of acid neutralization.

However, such schemes (e.g., Rau et al. 2013) require loss of SO_4^{2-} (or Cl^- in the case of HCl use) and thus a continuous supply of (expensive) sulphate would be required. To overcome this challenge, the sulphate can be recycled first as an acid and then as a metal sulphate and back again (Lammers et al. 2023). For example, a monovalent salt solution, e.g., Na_2SO_4 , can be electrolyzed or electro-dialyzed to generate H_2SO_4 that is again used to leach metal salts from minerals, but where the NaOH produced in the catholyte is used exclusively to precipitate less soluble polyvalent metals as metal hydroxides (Fig. 7), with the then reformed Na_2SO_4 recycled as brine/electrolyte. In this way Na_2SO_4 is (largely) conserved and the metal hydroxide precipitates could then be used as an alkalinity source for OAE if they are at least partially soluble in seawater.





Figure 7. Example of the indirect production of solid, polyvalent metal hydroxides from minerals and water using electro-dialysis or electrolysis of a monovalent salt. H_2 and O_2 are also produced.

Another alternative is to use dissolved metal sulphates produced from the mineral/acid leaching directly as electrolyte/brine in cells where the subsequent precipitation of metal hydroxide inside the cell is avoided or otherwise accommodated (Fig. 8). This could include continually harvesting e.g., $\text{Mg}(\text{OH})_2$ or $\text{Ca}(\text{OH})_2$ precipitated on or near the cathode (Pan et al. 2018, Sano et al. 2018) and/or using diaphragms (Kelland et al. 2022) or membrane-less cells (Talibi et al. 2017) to avoid membrane fouling by precipitates. Compared to the process in Fig. 7, this method more directly generates hydroxides from mineral sources and water.

Formatted: Subscript

Formatted: Subscript



305 Figure 8. Example of the direct use of metal salts acid-leached from minerals in the electrochemical production of alkalinity for OAE.

3.2.3 Considerations for best research practices

In this section, we highlight key parts of the brine-to-alkalinity OAE process where the application of best practices is especially critical to performing reproducible research.

310

Brine treatment: The aqueous brine source input into the electrochemical unit for the generation of alkalinity is often seawater, reverse osmosis concentration (ROC), or some other brine stream that also contains the divalent cations Ca^{2+} and Mg^{2+} . Because the electromechanical systems used for this purpose have compartments with high pH values (> 13), care must be taken to avoid the precipitation of solid $\text{Mg}(\text{OH})_2$ and/or CaCO_3 within the electrochemical unit, as this can lead to increasing voltages, current shunting, and increased hydraulic pressure. Some combination of pre-treatment to decrease the concentration of divalent cations and periodic, acidic clean-in-place flushing can avoid this problem. Examples of pre-treatment methods include, but are not limited to, ion exchange and the use of precipitation softening via $\text{NaOH}_{(\text{aq})}$ addition.

315

Alkalinity generation: In practice, the generated alkalinity may have a more complex ionic composition than the simplified description provided above, depending on the input brine composition and the properties of the electrochemical system such as membrane permittivity and selectivity. For example, because seawater contains K^+ ions and because cation exchange membranes allow K^+ and Na^+ transport, the alkalinity generated from the electrochemical processing of seawater will not be pure $\text{NaOH}_{(\text{aq})}$ but will also contain some fraction of $\text{KOH}_{(\text{aq})}$. This means that in-line measurement proxies of the generated alkalinity such as conductivity and pH should be calibrated by offline measurements such as TA titrations and inductively coupled mass spectrometry (ICP-MS). Sampling ports built into the electrochemical system are recommended for this purpose.

325

Aqueous alkalinity dispersal: As previously mentioned, the ratio of the rate of alkalinity addition to the rate of dilution must be kept low to avoid the precipitation of $\text{Mg}(\text{OH})_2$ or CaCO_3 within the mixing zone. The carbonate chemistry and turbidity

should be continuously monitored near the point of dispersal. Precipitation will manifest as a decrease in TA and increase in
330 turbidity (see Chapter 4).


Energy cost, CO₂ emissions, and economics: In order for research on electrochemical OAE to be relevant to CDR performed
at globally relevant scales, it is necessary to document or estimate the energy use, CO₂ emissions, capital costs and operating
costs that are incurred in small-scale systems, and particularly how these would scale for larger systems. These are essential
335 for making informed decisions regarding future RD&D allocations and ultimately decisions about when and where the most
cost-effective methods might be deployed.

Environmental and societal impacts and benefits: So as to better inform decision makers, researchers must assess how land,
air, ocean and societal systems might be affected by electrochemical OAE. This includes the environmental and societal
340 consideration of: (i) Land and resource use such as mineral/salt/brine/water extraction, transportation, processing and refining;
(ii) The footprint of the facility and its operation; and (iii) The downstream impacts/benefits of the products. Researchers
should aim to produce a comprehensive budget of all fluxes across the system boundaries (inputs and outputs of energy and
matter) to enable this assessment (see Chapter 5).

3.3 Accelerated Weathering of Limestone as an OAE Strategy

345 3.3.1 Technical summary

In a process called Accelerated Weathering of Limestone (AWL), calcium carbonate (derived from carbonate-bearing rocks,
e.g., limestone) can be spontaneously carbonated in the presence of elevated pCO₂ and seawater to form predominantly calcium
[and](#) bicarbonate ions in seawater (Rau and Caldeira 1999) via the reaction (Reaction 5):



where the molar quantities relative to CaCO₃ are approximately: a = 0.65, b = 0.74, c = 1.48, and d = 0.17, e = 0.18 when re-
equilibrated with typical seawater at [pH 8.1 and at](#) a p-CO₂ = 420 μatms. The preceding quantities are halved when expressed
355 in units of moles per mole of alkalinity since 1 mol of CaCO₃ = 2 mols alkalinity. This implies a maximum tonnes CO₂ removal
per tonne CaCO₃ of about 0.29 or a minimum requirement of about 3.5 tonnes of CaCO₃ per tonne CO₂ captured and stored.

While AWL is an OAE scheme, given the requirement of elevated CO₂ to spontaneously drive reaction 5, it has been more
widely considered as a CO₂ emissions reduction technology, analogous to CCS, at coastally located, fossil-fuelled power plants
(Rau and Caldeira 1999, Caldeira and Rau 2000, Rau et al. 2007, Langer et al. 2009, Rau 2011, Haas et al. 2014, Chou et al.

360 2015, Kitchner et al. 2020a and b, Caserini et al. 2021, Xing et al. 2022). However, this approach can be relevant to CDR if
the concentrated CO₂ used is from: i) emissions from biomass respiration, energy (electricity) production, gasification or
fermentation, ii) direct air capture, iii) natural emissions from hydrothermal or geothermal activity or iv) possibly natural or
artificial upwelling of deep seawater whose pCO₂ is high enough and a CaCO₃ saturation state low enough to facilitate CaCO₃
dissolution.

365

The CO₂ must be of sufficient concentration so that when equilibrated with water or seawater, CaCO₃ undersaturation in the
solution is ~~affected-effected~~ and the reaction can spontaneously proceed. Calculations using CO₂SYS (Pierrot 2006) suggest
that surface seawater equilibrated with a p-CO₂ greater than about 2500 μatms is required for CaCO₃ undersaturation to occur
and for the reaction to spontaneously proceed. Sufficiently elevated p-CO₂ drives down solution pH and thus [CO₃²⁻] to achieve
370 a CaCO₃ saturation state that is corrosive to CaCO_{3s}. The higher the p-CO₂ the lower the pH, [CO₃²⁻], and CaCO₃ saturation
state (Ω_{cal}) and hence the faster the kinetics of the reaction, the greater the areal and volumetric reaction rates achieved, and
the higher the DIC concentration attained. Experiments have shown reaction rates ranging from about 10⁻⁷ to 10⁻⁵ mols m⁻² of
mineral surface sec⁻¹. Since volumetric reaction rates are sensitive to carbonate mineral surface area per reaction volume, the
interplay among carbonate particle size, seawater and gas contacting, and flow rates dictate reactor design, size and
375 performance (Rau 2011, Kirchner et al. 2020a, Xing et al 2022).

Once the calcium bicarbonate+carbonate ions are formed and discharged into the ocean it is presumed that the longevity and
security of the storage will be equivalent to that of the existing alkaline C in the ocean, on the order of 100,000 years
(Middelburg et al. 2020). This assumes that the AWL reaction (R5) will not be reversed prematurely by enhanced biotic or
380 abiotic CaCO₃ precipitation. Biotic calcification in some marine taxa has been shown to increase with increasing alkalinity
and rising calcium carbonate saturation state, Ω_{cal} (Albright et al. 2016, Renforth and Henderson 2017, Gore et al. 2019). Note
that calcium carbonate saturation state will be more sensitive to the addition of Ca (bi)carbonate than non-Ca alkalinity since
both Ca²⁺ and CO₃²⁻ are being added: Ω_{cal} = [Ca²⁺] [CO₃²⁻]/K_{sp} where K_{sp} is a temperature, salinity, and pressure sensitive
solubility constant for calcite. Thus, on a per mole basis, the threshold for carbonate precipitation will be more rapidly reached
385 with calcium-based alkalinity addition relative to the addition of other forms of dissolved metal (bi)carbonates (Fig. 9).





Figure 9. Ω_{ca} (= the saturation state of calcite) response to calcium-based vs non-calcium-based alkalinity added to seawater initially containing 2350 μM total alkalinity (=TA) and equilibrated with a $p\text{-CO}_2$ of 420 μatms . Modelled using CO₂SYS (Pierrot 2006) modified to account for variable $[\text{Ca}^{2+}]$.

Formatted: Superscript

390 An additional feature that will further promote carbonate precipitation is the degassing of the excess CO_2 from the carbonated solution once exposed to air. This in effect removes acid from the carbonated solution, raising pH, $[\text{CO}_3^{2-}]$ and Ω_{cal} . An example of the chemical sequence of events in carbonating seawater using AWL and then re-equilibrating the carbonated seawater with air is shown in Fig. 10.



395 **Figure 10.** Example of the chemical progression of AWL starting first with representative, ambient seawater at $p\text{-CO}_2=420 \mu\text{atms}$,
 followed by equilibration with CaCO_3 s and a $p\text{-CO}_2$ of 10,000 μatms followed by re-equilibration with air $p\text{-CO}_2=420 \mu\text{atms}$. A) DIC
 = total dissolved inorganic carbon; TA = total alkalinity. B) Ω_{ca} = the saturation state of calcite. Modelled using CO₂SYS (Pierrot
 2006) modified to account for variable $[\text{Ca}^{2+}]$.

Here the net addition of 2150 μM of dissolved calcium (bi)carbonate in equilibrium with an excess of CaCO_3 s -and a $p\text{-CO}_2$
 400 of 10,000 μatms yields a transfer of carbon from the gas to seawater of 2679 μM , about 310 μM of which is in the form of
 $\text{CO}_{2(\text{aq})}$. If this solution was then added to the surface ocean and allowed to re-equilibrate with air $p\text{-CO}_2=420 \mu\text{atms}$, pH would
 rise above that of the initial seawater (by about 0.24 units) and stored carbon would decline from its high value following
 carbonation by about 35%, resulting in a net C storage from the AWL process of 1739 $\mu\text{M C}$ (Fig. 10A). In a full-scale facility,
 Kirchner et al (2020b) modelled a 50% loss of captured carbon following an AWL discharge. The percentage of captured CO_2
 405 lost will very much depend on the $p\text{-CO}_2$ of the gas used as well as the degree of chemical equilibration achieved among gas,
 carbonate and seawater. Use of high CO_2 and its equilibration with seawater, but with incomplete equilibration with carbonate
 minerals will result in an AWL discharge solution with high DIC largely as $\text{CO}_{2(\text{aq})}$, but with relatively little additional alkaline
 C formed (little long-term C storage).

410 Upon equilibration with air, the loss of excess CO_2 from the above alkalized seawater forces a rise in Ω_{ca} to 14.5 in the
 above example (Fig. 10B). This is >3X higher than the initial ambient seawater and could cause spontaneous CaCO_3

precipitation from seawater. However, such an effect is likely countered by the rapid dilution of the carbonated solution with ambient seawater relative to the slow kinetics of CaCO_3 precipitation (Fig. 7 in He and Tyka 2023). As long as dilution occurs faster than $\text{CaCO}_{3(s)}$ formation, $\text{CaCO}_{3(s)}$ precipitation and alkalinity loss can be avoided (He and Tyka, 2023).

415

The limitations of this approach in the context of OAE CDR include the need for a concentrated non-fossil CO_2 source in close proximity to seawater and carbonate minerals. Potential mineral carbonate sources include globally abundant limestone as well as less abundant dolomite and magnesite. Waste marine shell material or carbonate sands can also be considered, especially because aragonitic shell material should be more soluble than calcite (e.g., limestone) and that this aragonite dissolution simply speeds up the natural return of its marine-derived constituents to seawater. Proximity to the ocean is also a requirement both for the water used for carbonation ~~and as~~ well as for discharge and storage of the carbonated, alkalinized seawater. Also, considering a possible upper limit of only about 25 mg C stably stored/L of seawater, significant pumping of seawater to facilitate gas/carbonate contacting and conversion must occur. Mining, processing and transportation of $>3.5 \text{ t CaCO}_3 \text{ t}^{-1}$ CDR also needs to be considered as does the size and capital and operating costs of the seawater/ CO_2 /carbonate contactor. For one AWL design, Xing et al. (2022) estimate an energy cost of 5.7–8.2 GJ and a land requirement of 7.1–13.1 m^2 per tonne of CO_2 captured and stored, after allowing for degassing of the carbonated seawater following discharge in the ocean.

420

425

Advantages of the process include: i) spontaneous, exothermic conversion and long-term storage of CO_2 , ii) ocean alkalization and thus restoration of ocean pH, iii) relative ease of verifying CDR by carbonating alkalinity prior to release and quantifying the increase in carbon concentration in solution prior to release rather than having to verify CDR occurring in the ocean, and iv) providing a relatively simple, low-tech, widely applicable approach to OAE at coastal sites.

430

In sum, considering the global abundance of concentrated CO_2 waste streams, calcium carbonate mineral resources (including massive waste piles (Langer et al. 2009)) and the reactivity of these minerals in elevated $\text{CO}_{2(aq)}$ solutions, AWL seems an effective way to perform relatively safe, low-cost, low-tech OAE at scale, especially considering that it is routinely used at small scales to alkalize saltwater aquaria (Huntington 2002) and considering that such spontaneous rock/water/ CO_2 reactions provide the primary source of alkalinity naturally present in the global ocean (Middelburg et al. 2020). Its use in CDR is, however, more restricted considering that the CO_2 used must be concentrated above that in air in order to make the CDR rate relevant on human timescales. Further research is needed to better determine the desirability, effectiveness and capacity of AWL.

435

440

3.3.2 Considerations for best research practices

Purity of feedstocks Any impurities in the feed CO_2 or carbonate mineral has the potential to be released with the discharge of the carbonated seawater. The quantity and impacts of these impurities need to be measured to assess the potential for

445 downstream environmental impact as well as reduction in reactivity per mass of mineral. For example, Kirchner et al (2020a) found measurable trace metal concentrations in their discharge originating from the limestone used, but all concentrations they considered were “below levels of environmental concern”. Only slightly elevated NO_3^- was observed in the discharge seawater that originated from the NO_x from the flue gas processed. [This study explored the dissolution of limestone in seawater driven by high \$\text{CO}_2\$ from a point source of fossil fuel combustion emissions rather than concentrated from the atmosphere, which and](#)
450 [it should be noted that these two cases may not have the same impurities.](#)

Formatted: Subscript

Monitoring Reporting and Verification. Because AWL carbonation likely occurs before addition to the ocean, the quantity of carbon captured and converted for long term storage can in theory be easily quantified as an increase in seawater DIC at point of discharge. This is especially true if the carbonated seawater is equilibrated with air prior to release to the ocean so that
455 excess dissolved CO_2 (that will ultimately be lost from seawater once released) is not counted as sequestered carbon (Fig. 2). Otherwise, the net CO_2 removed and stored can be measured/-calculated by either: i) bubbling with air a subsample of the freshly carbonated seawater and measuring its DIC upon [air equilibration \(e.g., indicated by attaining a stable pH higher than the initially carbonated solution\)](#) or ii) calculating DIC in air-equilibrated discharge by measuring temperature, salinity, pH, DIC and TA of the freshly carbonated seawater and then modelling its DIC at ambient air p-CO_2 . In each case the proportional
460 difference in DIC before and after air equilibration must be subtracted from the DIC of the carbonated seawater to yield long-term, gross carbon removed. Net carbon removal is obtained by subtracting all anthropogenic CO_2 emissions incurred in the performance of AWL from gross CDR: gross CDR – emissions = net CDR. Emissions includes those associated with carbonate extraction, processing and transportation; energy usage in water pumping and other operating activities; and infrastructure and maintenance of the system

465 Economics. Estimating the possible economics of AWL systems at scale is essential for making informed decisions on future RD&D. It requires extrapolating/modelling the costs measured or inferred at research scales. It is therefore important to record carbonate purity, energy usage and efficiency, volumetric reaction rates, water pumping requirements, etc so as to better estimate costs and performance at scale.

470 Environmental and social impacts. As in all OAE, the upstream and downstream environmental and social impacts of AWL must be considered at research and larger scales. In particular the impacts of:

- i) Increased carbonate mineral extraction and processing, though keeping in mind that limestone mining and processing has resulted in massive waste piles of carbonate material whose use could actually benefit land reclamation (Langer et al. 2009).
- 475 ii) Seawater pumping, screening and carbonation which can impact resident biota (CEC 2005). When possible, it is best to utilize existing seawater pumping (such as for power plant condenser cooling) to avoid additional [cost](#)/impacts of new pumping. If the CO_2 used for carbonation is hot (e.g., from exhaust from a biomass energy plant) this will warm the seawater, potentially affecting downstream biota.



480 iii) the purity of the carbonate minerals used, in particular the presence of any trace constituents that could have environmental
consequences downstream (Chapter 4). Likewise, the purity and temperature of the CO₂ used must be considered in evaluating
downstream impacts.

iv) the societal consequences of AWL activities including those associated with the upstream increased carbonate mineral
extraction, processing and transportation, the footprint of the AWL operation on land and any impacts occurring downstream
in the ocean (see Chapter 5).

485 3.4 Ocean Liming

3.4.1 Technical summary

Ocean liming is the process of adding lime (CaO) or hydrated lime (Ca(OH)₂) to the surface ocean (Kheshgi 1995, Renforth
et al., 2013), the dissolution of which increases seawater alkalinity (Reaction 6 and 7; Kheshgi 1995). Lime is conventionally
manufactured through the calcination of limestone at >800°C (Reaction 8) using fossil fuels and is used in a range of industries
490 including steelmaking, paper manufacturing, construction, and agriculture.



495

First proposed for OAE (Kheshgi 1995) the CO₂ produced from the kiln (from limestone decomposition and fossil fuel use)
must be captured and stored for the technology to result in a net- CO₂ removal (Fig. 11). However, energy requirements (<6
GJ tCO₂⁻¹) and the cost (\$70 - 160 tCO₂⁻¹) of ocean liming are consistent with other engineered CDR approaches (Renforth et
al., 2013). Others have shown that the integration of biomass and hydrogen energy vectors may improve the process carbon
500 balance and cost feasibility (Caserini et al., 2019).

Kiln technologies for CaO (often referred to as ‘burned lime’ or ‘quicklime’) production are diverse and include upright or
inclined shafts, rotating shafts, and parallel or contraflow introduction of fuel and feedstock. The selection of kiln type depends
on the product material characteristics, quality of the limestone feedstock, local market demand, fuel type and availability, and
505 finance availability (European Commission 2013).






Figure 11. A simplified process flow diagram of ocean liming (Renforth et al., 2013).

510 Limestone decomposes at high temperature by solid-state diffusion of CO₂ through the material. The resulting CaO retains the overall volume of the initial calcite but with increased internal porosity (Fischer 1955). As such it is possible to create lump lime (larger particles of lime produced from similarly sized feedstock limestone).

515 Powdered Ca(OH)₂ is produced by adding a stoichiometric volume of water to CaO ('hydration', if excess water is used this is referred to as 'slaking', Reaction 9). This hydration reaction is exothermic resulting in the breakdown of CaO to a fine powder of Ca(OH)₂. This is thought to be via a topochemical mechanism (Gartner 2018) which produces Ca(OH)₂ particles around 2-5 μm (Yakymchko et al 2020), these particles often form larger aggregates of 30-40 μm bound together by weak Van der Waals forces (Yakymchko et al 2020). They are also more porous than CaO resulting in a higher specific surface area (Moropoulou et al., 2001). There is some literature to suggest that the size of the particle may be controlled by the slaking temperature, (e.g., steam slaking Pesce et al., 2023). Furthermore, the fast reaction rates resulting from small particle size and high surface area are useful in most traditional applications, but may not be appropriate for ocean liming (see below)





525 **Figure 12. Global distribution of carbonate sedimentary deposits (data from Hartmann and Moosdorf (2012), and map adapted**
530 **from Renforth et al., 2022).**

Provided that the CCS is in place to capture the CO₂ emissions from limestone decomposition during calcination, OL can be carbon-negative even when current technology and not fully decarbonized energy is used. Specifically, an LCA on OL (Foteinis et al., 2022) revealed that the main environmental hotspots of the process were limestone calcination, where fossil fuel is consumed for heat generation, followed by CCS, which is energy intensive, while mining, hydration, and ocean spreading affected the environment impact to a much lesser extent. The LCA results were also sensitive to transportation means and distance (although carbonate sedimentary rocks are widely distributed, Fig. 12), and particularly to the kiln technology and fuel type during calcination. When best available technology is used, along with renewable electricity to drive the process (e.g., calcination using plasma torches), then OL's environmental performance is optimized. If the low-grade heat generated during hydration is also recovered and used for district heating, then avoided emissions could be also realized, which can be larger than the process life cycle emissions. In this sense, not only the full amount of CDR is credited to OL but also avoided emissions are achieved (Foteinis et al., 2022).

540 It is possible to create magnesium oxides and hydroxides, either through the calcination of magnesium carbonates (McQueen et al 2020) or through extraction from magnesium silicates (Renforth and Kruger 2013). While the calcination temperature and energy of magnesite is substantially lower than that of calcite, global reserves are approximately ~10 Gt (McQueen et al 2020), which suggests their exploitation at scale for ocean liming may be limited. Renforth and Kruger explore the coupling of mineral carbonation and ocean liming in which Mg is extracted from abundant silicate minerals through carbonation and then calcined to produce magnesium oxide/hydroxide materials (Fig. 13).




Figure 13. A coupled mineral carbonation ocean liming system proposed by Renforth and Kruger, 2013.

550 Processes have been suggested for the extraction of Mg from silicate minerals and the creation of $Mg(OH)_2$ for the purpose of capturing carbon dioxide from flue gasses (Madeddu et al., 2015, Nduagu et al., 2012), but may be suitable for OAE as well. Nduagu et al., (2012) suggest a multistep process in which serpentinite (a Mg rich rock) is heated at $400^\circ C$ with solid ammonium sulphate creating a solid magnesium sulphate and silica, and evolving ammonia and water as gas. The silica can be leached by washing the solid product with water, following which bringing the ammonia gas back into contact with the Mg sulphate creates high pH conditions in which $Mg(OH)_2$ can precipitate. An alternative approach, (Madeddu et al., 2015) heats solids of NaOH and an olivine rich rock at $180^\circ C$, forming $Mg(OH)_2$ and a Na silicate. Both approaches propose to use the $Mg(OH)_2$ for direct reaction with flue gas, and no work has explored their potential for OAE.

3.4.2 Considerations for best research practices

560 Lime/hydrated lime production: Lime can be easily created for small scale laboratory experiments by calcining limestone (or laboratory grade calcium carbonate) in a furnace at $900^\circ C$. It is possible to sinter lime at temperatures $>1,100^\circ C$, which would result in a lower reactivity. While sintering is often undesirable for commercial lime, the effect may be useful for OAE to reduce particle dissolution rate and prevent oversaturation of carbonate minerals in seawater. Lime products can also be sourced from commercial suppliers. The reaction of burnt lime (CaO) with water is highly exothermic and its fire-safety risk should be considered when storing or using in the laboratory.

Carbonation prior to experimentation: Lime and hydrated lime readily react with atmospheric CO_2 so should be produced or sourced as near to the start of the experimental work as possible. The materials can be stored in airtight and/or desiccated

containers to minimize carbonation. However, it is difficult (if not impossible) to limit carbonation and will certainly be present within commercially sourced material. Carbonate content should be measured (e.g., through mass loss on ignition) before the experiment.

Reactivity, spontaneous precipitation in seawater: Commercially sourced hydrated lime has been manufactured for applications in which high reactivity is desirable. Hartmann et al, (2023) have shown that additions of these particles (0.7 mg Ca(OH)₂: 1 g seawater) may result in spontaneous precipitation of carbonate minerals. Caserini et al., (2022) modelled an initial particle density of approximately 80 mg Ca(OH)₂: 1 g seawater, diluting to <0.6 mg Ca(OH)₂: 1 g seawater (assuming a 10 kg s⁻¹ addition through a single discharge nozzle in the wake of a ship) within about 30 seconds. Experiments that add hydrated lime to solution should use an initial concentration <0.7 mg Ca(OH)₂ assessing particle dissolution across as 10² - 10⁴/min range of dilution.

580

3.5 Hydrated carbonate mineral formation

3.5.1 Technical Summary

There are several hydrated carbonate minerals such as ikaite, monohydrocalcite, nesquehonite, hydromagnesite, and amorphous calcium carbonate that are undersaturated in the surface ocean and are thermodynamically likely to dissolve and increase alkalinity when added to seawater (Table 3-1). The occurrence of these minerals and a method for their industrial production is presented below,

Ikaite (CaCO₃·6H₂O) precipitates from aqueous solutions close to freezing conditions (Boch et al., 2015) in a narrow temperature range below ca. 4 – 8 °C and depending on ionic strength down to negative temperature values (e.g., in highly saline solutions down to –8 °C; Hu et al., 2014, Papadimitriou et al., 2014). Alternatively, elevated pressure conditions (>3 kbar at 25 °C) facilitate the crystallization of ikaite (Marland, 1975, Shahar et al., 2005). The solubility of ikaite is higher compared to the anhydrous calcium carbonate polymorphs calcite, aragonite and vaterite (Brecevic and Nielsen, 1993, Marion, 2001). Dissolved compounds such as magnesium, phosphate, sulphate, and organic molecules that inhibit the formation of anhydrous calcium carbonates, favour the nucleation of ikaite (Brooks et al., 1950, Bischoff et al., 1993b). Outside these restricted environments ikaite dehydrates and disintegrates rapidly, (within minutes to weeks), preferentially into more stable carbonate minerals and water (Mikkelsen et al., 1999). In some cases, calcite pseudomorphs after ikaite might persist (“glendonite”, Greinert and Derkachev, 2004).

Monohydrocalcite (MHC: CaCO₃·H₂O) is a rare mineral in geological settings (Nishiyama et al., 2013), but is frequently associated with other calcium and magnesium carbonate minerals, such as calcite, aragonite, lansfordite, and nesquehonite

600

(Nishiyama et al., 2013). Monohydrocalcite has been observed in air conditioning systems (Nishiyama et al., 2013), in 'moonmilk' deposits in caves (Nishiyama et al., 2013), and in beach sands formed from algal spume (Nishiyama et al., 2013). It has been reported as a significant component of the decomposition of ikaite in the towers of the Ikka Fjord, West Greenland (Nishiyama et al., 2013). Both laboratory studies and natural observations have indicated that the formation of MHC requires the presence of magnesium in the solution (Nishiyama et al., 2013), and possibly forming via an Mg-rich amorphous precursor (Nishiyama et al., 2013).

The magnesium carbonate mineral nesquehonite ($\text{MgCO}_3 \cdot 3\text{H}_2\text{O}$) precipitates at room temperature from supersaturated solutions rich in magnesium and bicarbonate (Hopkinson et al., 2008). It is metastable and transforms into hydromagnesite in ambient conditions (e.g., Kazakov et al. 1959), which may be responsible for some naturally occurring hydromagnesite (Davies and Bubela 1973). Mafic and ultramafic mining wastes, by virtue of their high calcium and magnesium content, are prone to forming numerous carbonate species upon contact with atmospheric CO_2 depending on the environmental conditions that prevail at the stockpiles, but metastable nesquehonite was reported to be the dominant magnesium carbonate forming in ambient conditions (Zarandi et al., 2017). Upon rising the temperature above 50 °C, nesquehonite evolves into thermodynamically more stable products with lower CO_2 :Mg ratios (Zarandi et al., 2017).

Hydromagnesite ($\text{Mg}_5(\text{CO}_3)_4(\text{OH})_2 \cdot 5\text{H}_2\text{O}$) is a naturally occurring hydrated magnesium carbonate (e.g., Königsberger et al. 1999). At the Woodsreef Asbestos Mine, New South Wales, Australia, weathering of ultramafic mine waste sequesters significant amounts of CO_2 in hydromagnesite ($\text{Mg}_5(\text{CO}_3)_4(\text{OH})_2 \cdot 4\text{H}_2\text{O}$) (Oskierski et al., 2021). Mineralisation of CO_2 in above-ground, sub-aerially stored tailings is driven by the infiltration of rainwater dissolving Mg from bedrock minerals present in the tailings (Oskierski et al., 2021). Complete dissolution of source minerals, or formation of Mg-poor products during weathering, is expected to transfer Mg into solution without significant alteration of the Mg isotopic composition (Oskierski et al., 2021). The main mineral sources of Mg in the tailings (silicate, oxide/hydroxide and carbonate minerals) are isotopically distinct and the Mg isotopic composition of fluids and thus of the precipitating hydromagnesite reflects both isotopic composition of source minerals and precipitation of Mg-rich secondary phases (Oskierski et al., 2021). The consistent enrichment and depletion of ^{26}Mg in secondary silicates and carbonates, respectively, underpins the use of the presented hydromagnesite and fluid Mg isotopic compositions as a tracer of Mg sources and pathways during CO_2 mineralisation in ultramafic rocks (Oskierski et al., 2021).

Amorphous calcium carbonate (ACC) is unstable under normal conditions and is found naturally in taxa as wide-ranging as sea urchins, corals, molluscs, and foraminifera. It is usually found as a monohydrate, holding the chemical formula $\text{CaCO}_3 \cdot \text{H}_2\text{O}$, however, it can also exist in a dehydrated state, CaCO_3 (Rodríguez-Blanco et al., 2011). ACC has been reported for over 100 years when a non-diffraction pattern of calcium carbonate was discovered by Sturcke Herman, exhibiting its poorly ordered nature (Rodríguez-Blanco et al., 2010). The structure and chemistry of ACC is complex with several forms of ACC classified

635 according to their water content, local order, and mode of formation (e.g., abiotic vs biogenic). A key variable is the amount of structural water. Hydrated-ACC can contain up to ~1.6 mol of water per mole of CaCO₃, yet several less hydrated and even anhydrous forms of ACC have been described (Rodriguez-Blanco et al., 2010; Bots et al., 2012).

Table 1 A summary of potential hydrated carbonate minerals for ocean alkalinity enhancement (see Renforth et al., 2022).

Hydrated carbonate mineral	Chemical formula	Reported occurrence	Gibbs free energy of hydration reaction from unhydrated forms ^a (kJ mol ⁻¹)	Gibbs free energy of dissolution reaction in seawater ^a (410 ppm @ 25°C) (kJ mol ⁻¹)
Monohydrocalcite	CaCO ₃ H ₂ O	Formation of MHC requires magnesium in the solution in spite of the incompatibility of magnesium into the MHC structure. Monohydrocalcite has been observed in air conditioning systems, and in moonmilk deposits in caves, both probably formed from spray of carbonate rich fluids.	4.0	-2.4
Ikaite	CaCO ₃ 6H ₂ O	Naturally occurring, metastable hydrated calcium carbonate mineral that forms in cold (<15C), alkaline, nutrient-rich waters.	10.2	-8.9
Nesquehonite	MgCO ₃ 3H ₂ O	The magnesium trihydrate carbonate nesquehonite readily precipitates from solutions of magnesium bicarbonate at room temperature.	17.1	-11.5
Hydromagnesite	Mg ₅ (CO ₃) ₄ (OH) ₂ 5H ₂ O	Hydromagnesite is an abundant naturally occurring magnesium hydroxyl carbonate (e.g., Königsberger et al. 1999; Russell et al. 1999; Edwards et al. 2005b) that constitutes a large and potentially reactive sink for C.	16.9	-28.9

Hydrated amorphous calcium carbonate	CaCO ₃ xH ₂ O	ACC is unstable under normal conditions and is found naturally in taxa as wide- ranging as sea urchins, corals, molluscs, and foraminifera.	-	-
Calcite	CaCO ₃	Naturally abundant in limestone	-	1.6
Magnesite	MgCO ₃	Accessory mineral in limestone, alteration product in weathering of ultrabasic rock	-	5.7

a. Negative values denote an exothermic/spontaneous reaction.

640

Hydrated carbonate minerals are relatively rare and thus insufficient to meet the demand of a scaled up OAE industry. As such, they would need to be created. Renforth et al., (2022) suggest a process by which limestone is dissolved in water in an elevated CO₂ pressure reactor (~2 bar). The water is then degassed in lower pressure reactors (~20 mbar) under vacuum to evolve/recycle the gaseous CO₂ and create conditions in which carbonate minerals are likely to precipitate from the solution

645 (Fig. 14). If the precipitation environment is cooled or in the presence of calcite precipitation inhibitors, then Renforth et al., (2022) suggest that ikaite will form.




Figure 14 A CO₂ pressure swing process for creating a hydrated carbonate (adapted from Renforth et al., 2022).

650

There are several benefits for considering hydrated carbonate mineral addition for OAE. The chemical energy imparted into lime or hydrated lime during production is released during its dissolution and carbonation in the surface ocean. This energy is impossible to recover. The production of hydrated carbonates requires considerably less energy.

3.5.2 Considerations for best research practices

655

Summary of method of precipitating hydrated carbonates: The multi-step system pressure system for its mass production (Fig. 14) may not be convenient or necessary for all laboratory studies that may want to consider the impact of ikaite dissolution on seawater biogeochemistry. Existing methods for precipitating hydrated carbonates involve the reaction of an alkaline liquid (usually NaOH or Na₂CO₃) with calcium or magnesium chloride (e.g., Lennie et al. 2004). It is not yet clear if characteristics of these materials differ from those that might be produced from a pressure swing system.

660

Stability of hydrated carbonates: The feasibility of using hydrated minerals for OAE requires that the produced mineral remains stable for sufficient time to be added to the ocean and dissolve. Similarly, experiments performed using hydrated minerals should have sufficient confidence that the materials added to seawater have not converted to more stable anhydrous polymorphs. If these minerals were to transform into calcite or magnesite before addition it could result in a reduction of alkalinity by seeding additional carbonate precipitation. Experimental work suggests that synthetic ikaite can be stable for days at low temperature and that it increases alkalinity when dissolved in seawater (Renforth et al., 2022).

665

Methods of detection: Hydrated carbonate minerals are identifiable by several techniques including Raman spectroscopy, Fourier Transform Infrared (FTIR) spectroscopy, X-Ray Diffraction (XRD), Electron Probe X-ray Microanalysis (EPMA) and Scanning Electron Microscopy (SEM).

Raman spectroscopy is a non-destructive method that requires little or no sample preparation. Moreover, all the bands related to carbonates in the mid-infrared region have characteristic positions which make it easy to differentiate from other minerals. Raman analyses of carbonates have long been used in mineralogical and geochemical research (see Kim et al., 2021 and references therein).

FTIR is rapid (a few minutes per sample), does not require hazardous chemicals, has a small sample requirement (~ 1 mg), and produces several distinguishable carbonate bands in its spectrum. Diffuse reflectance infrared Fourier transform spectroscopy (DRIFTS) is a form of FTIR with additional advantages compared to transmission FTIR. DRIFTS does not require sample dilution in infrared transparent material, thus reducing sample preparation time, its sample-holding microcells allow for fixed volumes, and the sample is recoverable after analysis. DRIFTS is a method that has been used for identifying and quantifying calcite and dolomite in natural sediments. Few studies have used spectroscopic techniques to quantify carbonate in non-carbonate geological matrices (Bruckman and Wriessnig 2013; Du et al. 2013; Tatzber et al. 2007).

XRD is the most commonly used tool for identification of major minerals. In addition to qualitative analysis, quantitative XRD is possible because the peak intensities of a given mineral in the diffractogram are proportional to the weight percent of that particular mineral in the sample. However, peak intensities are also a function of the mineral's absorption coefficient, particle size, degree of crystallinity and the preferred orientation of the sample, this means that compared to qualitative analysis quantitative XRD requires more specialized expertise to produce accurate results.

3.6 Mineral addition to pelagic coastal environments

3.6.1 Technical Summary

Using the ocean's surface waters (which refers to the mixed layer) for mineral addition to increase ocean alkalinity has been the focus of interest of numerous research projects (Renforth & Henderson, 2017), starting with exploring suitable minerals to achieve increased alkalinity while investigating potential side effects on marine life and ecosystems. An obvious problem for the community of researchers involved in OAE has been identifying and generating the particle type and size required to allow for dissolution, classically considered to be smaller than 63 μm (Hangx & Spiers, 2009). However, while this particle size is comparably easy and energy efficient to produce, residence times in the water column would for most minerals be too short to allow for dissolution and particles would sink out too rapidly. To avoid mineral loss via sinking, particle sizes of $<1\mu\text{m}$ would

700 be required (Köhler et al., 2013), which are difficult to produce in a climate-neutral manner, and their application might be harmful for humans leading to respiratory problems (e.g., Doelman et al., 1990). One way to work with bigger grain sizes is to turn to coastal systems, where particles would sink to the seafloor and be transported back into the water column by natural turbulence, allowing for increased dissolution over time.

705 Classically, silica minerals such as olivine (forsterite or fayalite) and carbonate sedimentary rock such as limestone [and dolostone \(dolomite\)](#) have been suggested to increase alkalinity in an efficient way (Renforth & Henderson, 2017). However, large scale experiments are still a rarity (see also Riebesell et al., 2023, this Guide and Cyronak et al., 2023, this Guide). Other possible minerals for this purpose are basalt or serpentine. When choosing minerals, an ambition should be to ensure availability near the application location to reduce the carbon footprint, thus limiting the choice of mineral and again
710 emphasizing the advantage of coastal applications as compared to open ocean applications.

Another concern when applying alkaline minerals is the stability of alkalinity due to possible formation of carbonate phases. This results from the ocean's supersaturation in calcite and aragonite (Sarmiento & Gruber, 2006). If an increase in alkalinity is introduced along with an increase in carbonate ion concentrations, the supersaturation would increase even more, which has
715 been suggested to lead to solid carbonate precipitation (Fuhr et al., 2021, Moras et al., 2022; Hartmann et al., 2023). This, in turn, would decrease surface alkalinity causing an effect opposite to the desired one, [whereby the decrease in alkalinity would depend on the mineral used](#). One proposed solution to address this challenge is the application of CO₂-equilibrated alkaline solutions to minimize the risk of losing alkalinity due to carbonate phase formation.

720 Open-ocean and water-column silicate mineral applications have the potential to increase both the chemical and the biological carbon pump. Here, the biological carbon pump was of interest due to its potential to remove CO₂ on a timescale of several thousands of years (Longhurst et al., 1995, Petit et al., 1999, McNeil et al., 2003). The line of reasoning was often based on Earth's historical considerations, with cold periods in Earth history having been related to increased photosynthetic activity by phytoplankton (Kirschvink, 1992, Penman & Rooney, 2019). However, recent studies suggest that mineral additions can,
725 besides benefits, also pose risks to marine life, including primary producers (Glass & Dupont, 2017, Bach et al., 2019). This effect is likely related to the increased concentrations of trace metals enriched in the minerals of choice. Earlier dissolution experiments with olivine have shown that an increase of alkalinity of about 100 μmol L⁻¹ led to an increase of ~3 μmol Ni L⁻¹ due to non-stoichiometric dissolution of the heterogeneous material, this equals to approximately 3 times the natural concentration in seawater (Montserrat et al., 2017), within the toxic range for many eukaryotic microalgae (Glass & Dupont,
730 2017). Other trace metals present in alkaline minerals, including Cu, Cd, Cr, or other heavy metals, (Simkin & Smith, 1970, Beerling, 2017) have less clearly understood effects. Anthropogenic materials including from mining or cement production could also contain a variety of trace metals at concentrations yet to be determined, which might become particularly problematic to organisms of higher trophic levels in which they accumulate (Garai et al., 2021).

735 It is essential to consider whether the added minerals remain in the water column and impact the growth of the vital primary producers in the food web. Another important consideration is whether adding alkaline minerals impacts the local communities in the treated area and leads to any changes. Moreover, a possible change in the local communities might see the appearance of organisms that release other greenhouse gasses, potentially offsetting the sequestration achieved through the treatment.

740 Careful considerations have to be undertaken in order to ensure safe-minimum standards. One important aspect is that field applications cannot exceed environmental quality standards (EQS, (European Commission, 2017)). EQS defines the threshold concentration of potentially harmful toxic metals, like nickel and chromium. The impact of minerals enriched in those trace metals on biodiversity and ecosystem function is difficult to study, as minerals are not necessarily homogeneous and contain similar trace metal concentrations. Trace metal concentrations, however, may limit the amount of mineral addition, especially of olivine-rich rocks that can be deployed in marine habitats (e.g., Flipkens et al. (2021)). The potential difficulty arising from introducing toxic compounds is likely less pronounced in open ocean environments due to export and rapid dilution. Coastal environments can have limitations, especially with regard to sediments, which already have a (natural) background in trace metals and accumulate trace metals over time (see chapter 3.6.2). Furthermore, seawater pH should be kept within a natural seawater range (pH<9; Pedersen and Hansen, 2003). Even though phytoplankton can be adapted to a wide range of pH, the growth rates of a majority of species can be influenced significantly (Hinga, 2002, Penman & Rooney, 2019). In addition, a pH > 9.5 can promote the precipitation of aragonite, as well as brucite together with phosphorus and silicate (Hartmann et al., 2023). On the other hand, depending on the deployed material, specific plankton groups might benefit from, for example, iron additions (Boyd & al., 2000).

755 To scrutinize the effect of OAE as a tool to mitigate climate change, it is necessary to also investigate the impact of mineral addition, pH and alkalinity changes on non- CO₂ greenhouse gas production. Two important greenhouse gasses are methane and nitrous oxide, with warming potentials of approximately 70 and 300 times that of CO₂, respectively (Bange, 2006). While the ocean is a minor source of methane to the atmosphere, it contributes about one third of nitrous oxide emissions to the atmosphere (Bange, 2006), making it critical to understand any potential impacts of OAE on its formation. N₂O is chiefly produced biologically, with the microbes producing it known to be sensitive to changes in pH (Thomsen et al., 1994, Seeländer, 2023), however, so far, the few available studies indicate a reduction in N₂O production if pH and alkalinity are increased.

When considering the technical challenges within the pelagic environment for OAE, one of the primary considerations is how to effectively measure the CO₂ offsets generated from techniques that utilize the pelagic environment, therefore a standardization of MRV (measurement, reporting, and verification) is a necessity to secure procedures that ensure the accuracy and precision of measurements (see also Ho et al., 2023, this Guide). Within that, a reliable and well-established analysis technique for determining relevant parameters (e.g., alkalinity) is required to ensure the accuracy and comparability of data.

Ecosystem diversity in pelagic environments will vary according to the location because of the biological, chemical and physical parameters, due to for example ocean currents, temperatures, wind etc. Therefore, considerations from many disciplines are essential to explore the complexity.

To carry out coastal pelagic OAE research an understanding of benthic-pelagic coupling is required to assess the impact on benthic systems and ecosystems, and to be able to maximize the use of this coupling for OAE. Further, it is critical to assess the local and regional biodiversity by means of meta-omics, flow cytometry or similar high-resolution methods for microbial life to then understand what thresholds for trace metal additions would introduce toxic effects as defined in Bach et al. (2019) and references therein. For macro-lifeforms, targeted ecotoxicological assessments are required to avoid damage to, and heavy metal accumulation in, top-predators, and to establish robust thresholds.

3.6.2 Considerations for best research practices

Application of particles is challenging, (see also 3.7.2), as small sizes are required to assure water column dissolution, but larger particles (~63 μm) can be used if the goal is to achieve OAE in both the benthic and pelagic parts of a coastal system, where resuspension of particles can be useful to achieve mixing. However, any particle addition might lead to shadowing thus impacting photosynthetic organisms in the pelagic and benthic realm, requiring a thorough understanding of both, benthic and pelagic primary production, to avoid harming the basis of the ecosystem. In addition, mechanical stress can be imposed on benthic organisms by adding particles, data, however, is limited, here, and will have to be gathered for every system, individually.

While those effects will vary largely for each ecosystem, trace metal toxicity can be avoided. Before particles are added, we recommend a thorough analysis of the major elements in the mineral of choice to quantify the effect of mineral addition on the total alkalinity change potentially obtained in the system, but also to define the upper limit of additions with respect to trace metal toxicity. For some organisms, including pelagic primary producers, thresholds are available from the literature, however, to understand the impact of trace metal toxicity on complex food webs testing before application should be carried out in mesocosms and benthocosms containing assemblages or subsets of the natural communities present in the ecosystem of choice. At a minimum, key species should be tested individually for their trace metal (and pH) tolerance to avoid damage to biodiversity.

3.7 Addition to the coastal seafloor

3.7.1 Technical summary

800 Continental shelves comprise only about 7% of the global surface ocean, yet account for up to 30% of the oceanic primary production (Gattuso et al., 1998) and between 10 and 25% of the present-day CO₂ uptake (Regnier et al., 2013). Shelves are also important areas for cation and TA turnover related to detrital mineral dissolution and authigenic carbonate and clay precipitation (e.g., Linke et al., 1994; Jeandel et al., 2011; Jeandel & Oelkers, 2015; Torres et al., 2020). Assuming an ice-free surface area of continental shelf seas of 22x10⁶ km², natural carbon uptake in coastal waters has been estimated to be -0.19 Pg Cyr⁻¹, showing the importance of shelves as a natural global sink of atmospheric CO₂ (Laruelle et al., 2014, 2018).

805 The addition of ground minerals to the shelf seafloor may enhance this uptake even further, and as such are candidate locations for OAE. Large-scale mineral application would be logistically convenient, either using excavators directly on the beach or from small vessels or barges in offshore shallow waters. Several companies and initiatives already take advantage of this relatively easy CDR-implementation and study the effectiveness of mineral dissolution in the field.

810 The most obvious advantage of adding particulate minerals to the seafloor compared to the water column is the required grain size. Compared to water column deployment, for which the required grain sizes are <1µm in order to avoid rapid sinking (Hauck et al., 2016), the optimum grain sizes needed for seafloor deployment are proposed to range between 0.2 and 1.4mm (Schuiling & de Boer, 2011, Strefler et al., 2018), which is economically attractive. However, these recommendations lack thorough experimental testing, both in the laboratory and in the field.

815 Further, the choice of grain size depends on the region of deployment. Two potential coastal regions for mineral addition are low- and high-energy environments (modified after Meysman & Montserrat, 2017) (Fig. 15). High-energy environments are characterized by extensive water mass movement, such as surf zones, thereby providing a natural grinding mechanism allowing larger, less costly, grain sizes to be used (Meysman & Montserrat, 2017). In contrast, low-energy environments require the addition of smaller grain sizes (~20 to 100µm) as a higher surface area maximizes mineral dissolution (Oelkers et al., 2018). In this environment, mineral dissolution is enhanced by biota through bioturbation and microbial metabolism (Meysman & Montserrat, 2017). These two distinct environments are discussed below with respect to their advantages and disadvantages.




Figure 15 High- and low-energy environments with different regional advantages favouring mineral dissolution.

825

High-energy environments: These environments are located along the coastal surf zone or the shallow shelf, where wave action, currents and tidal activity lead to natural mineral erosion. The required grain sizes can be relatively large (mm -scale) for this environment, given that the constant movement naturally grinds the minerals, continuously exposing fresh reactive mineral surfaces and enhancing dissolution. Given that alkalinity enhancement directly occurs close to the air-sea interface in these well-mixed shallow water settings, the impact on atmospheric CO₂-uptake is immediate.

830

Detection of mineral dissolution and alkalinity production in these high-energy environments is challenging due to rapid mixing, dilution and dispersal of solutes. Minerals may also be transported along- and offshore away from their deployment location. This requires carefully designed field experiments to assess the efficiency of this OAE approach with regard to CO₂ draw-down (see section 3.7.2. and Cyronak et al., 2023, this Guide). Furthermore, these factors hamper accurate evaluation concerning MRV for commercial carbon removal purchases (see Ho et al., 2023, this Guide). An advantage of mineral dissolution in coastal surface sediments is the lower risk of secondary mineral formation. In an open environment, supersaturation levels potentially triggering carbonate or phyllosilicate precipitation in conjunction with other relevant factors (e.g., pH, DIC, TA) are more unlikely to be attained. CO₂-consumption may therefore be more efficient compared to low-energy environments. See Table 3.2 for a summary of advantages and disadvantages for mineral deployment in high-energy environments.

835

840

Low-energy environments: Shelf environments comprise the waters below the wave base down to 200m that are not significantly affected by normal wave action. The continental slope and deep seafloor are not considered here given that the exchange of bottom waters with surface ocean waters may be too slow to be relevant for near-term CO₂-reduction strategies (Smith et al., 2023).

The shelf sediment is mostly sand and mud (Schulz & Zabel, 2006), providing an ideal environment for mineral dissolution by taking advantage of the 'benthic weathering engine' (Meysman & Montserrat, 2017). Here, two mechanisms can be distinguished that potentially accelerate mineral dissolution, that is, microbial metabolism and bioturbation by macro-organisms.

The degradation of organic matter by microbial activity in fine-grained sediment creates a unique microenvironment that may be conducive to dissolution of some types of minerals. The microbial degradation of organic matter by aerobic and, in particular, anaerobic remineralization pathways (e.g., denitrification, iron- and manganese reduction and sulphate reduction) leads to an accumulation of reduced forms of S, N, Fe and Mn in both the dissolved and particulate phases. If these compounds are exposed to oxygen or nitrate at the sediment surface they can be oxidized rapidly, leading to a local decrease in pH to <6. Under these conditions, carbonate dissolution may take place if pore_waters-fluids become undersaturated with respect to the dissolving mineral phase (Jahnke & Jahnke, 2000). Silicate dissolution strongly depends on the mineral type, whereby Mg-silicate dissolution (e.g., olivine) is enhanced at low pH and aluminosilicates at high pH (Oelkers et al. (2018) and references therein). Mineral dissolution may be facilitated or even enhanced through the action of electrogenic cable bacteria that can oxidize S by shuttling electrons from subsurface anaerobic sediments to the oxic surface layer (Meysman et al., 2019). However, cable bacteria are not thought to be highly active in bioturbated sediments, such that their potential impact on alkalinity enhancement by mineral dissolution may not be quantitatively significant at the regional scale.

The effect of burrowing by large macroorganisms, known as bioturbation, enhances mineral incorporation into the sediment matrix and, consequently, bringing the minerals in contact with the acidic pore fluids and enhancing benthic-pelagic exchange (Neumann et al., 2021). Additionally, the digestive systems of macroorganisms, with their high enzymatic activity, low pH, mechanical abrasion, and digestion has been shown to increase silicate and carbonate dissolution (Cadée, 1976; Volkenborn et al., 2009). However, this process is poorly understood and its significance for mineral dissolution is unknown at regional scales.

A large drawback of the low-energy benthic environment for OAE is the high probability of secondary mineral precipitation. Formation of authigenic carbonates or phyllosilicates releases CO₂ (e.g., Wallmann et al., 2008; Torres et al., 2020) and directly counteracts the envisioned TA release and CO₂ uptake by mineral addition. Authigenic aluminosilicate formation was recently found to be a large Si sink in the global marine Si cycle, releasing CO₂ and consuming TA (e.g., Wallmann et al., 2008;

Rahman et al., 2017; Tréguer et al., 2021) on time scales of weeks to months, that is, much faster than previously considered (10³ years) and impacting element cycles on human timescales (Geilert et al., 2023). Authigenic, inorganic carbonate precipitation at the sediment-water interface or within the sediment column is triggered by alkalinity production from anaerobic microbially-mediated reactions (Sun & Turchyn, 2014) and can also be caused by silicate dissolution, buffering the potential pH drop induced by methanogenesis and by that creating carbonate saturated environments (Torres et al., 2020). In the context of mineral addition to increase ocean alkalinity, these secondary mineral formations may play a major role in the net CO₂-sequestration efficiency, as recently shown in laboratory experimental studies (Fuhr et al., 2022; Moras et al., 2022; Hartmann et al., 2023). Further research is required to identify the probability and impact of secondary mineral formation on net CO₂-turnover with respect to OAE (Table 3.2 and Chapter 3.7.2). The results from laboratory studies though (Fuhr et al., 2022; Moras et al., 2022; Hartmann et al., 2023) are still debatable with regards to their transferability to the open ocean where secondary mineral saturation states are reached less easily. Mesocosm studies might offer a solution here (Riebesell et al., 2023, this Guide), in which open ocean conditions can be simulated more realistically and the triggering factors for secondary mineral formation be identified (see also Chapter 3.7.2).

As in the high-energy shallow environments, detection of mineral addition in deeper and fine-grained coastal waters (50 – 200 m) can be difficult. The deployment of autonomous instruments on the seafloor, such as benthic chambers, can be used to measure fluxes of alkalinity and other dissolved compounds to/from the seafloor. Depending on the nature of the sediment and the carbon degradation rates, benthic chambers can typically detect O₂ consumption and nutrient release on timescales of 1-2 days of continuous deployment in shelf environments (Sommer et al., 2016). However, the attribution of mineral dissolution to changes in alkalinity is challenging, particularly against the large seawater alkalinity background. Only in the most reactive coastal settings such as upwelling areas can alkalinity fluxes be determined accurately (Ilyana et al., 2013; Dale et al., 2015). The development and incorporation of high-precision pH and p CO₂ sensors may provide a solution to detecting small changes in CO₂ and alkalinity fluxes due to mineral dissolution. To our knowledge, the suitability of benthic chambers with respect to detection of OAE at the seafloor still requires field testing.

For both high- and low-energy environments, the risk exists that the alkaline minerals will not remain at the site of deployment, either due to seabed erosion by wave action and currents, transport or by burial. In areas where there are strong bottom currents, fine-grained minerals can be eroded and transported. These minerals are then ultimately delivered to regional depocenters in deeper basins in shallow coastal seas such as the Baltic Sea (e.g., Wallmann et al., 2022) or to the continental slopes on open margins (e.g., Anderson et al., 1994). Once deposited in deep waters, they are removed from the shallow regions where the benthic-pelagic water mass exchange is rapid.

A final point for consideration is the sedimentation rate. On the one hand, high particulate organic carbon (POC) sedimentation rates are desirable to guarantee high rates of organic matter degradation and low pH pore waters/fluids necessary for enhanced

mineral dissolution. On the other hand, ~~too~~ high sedimentation rates of detrital minerals or low POC sedimentation rates may be counterproductive, leading to rapid burial of OAE-minerals below the dissolution zone. These factors need to be factored into the cost-benefit analysis of envisaged OAE mineral deployment in low-energy environments.

915 **Table 2 Advantages and disadvantages of coastal marine mineral addition on the continental shelf (low energy environment) compared to the surf zone (high-energy environment).**

	Low-energy environment (continental shelves)	High-energy environment (surf zone)
Mineral dissolution enhanced by	metabolic processes Bioturbation	wave actions, tides and currents
Mineral size	medium (μm -range)	large (mm-range)
Grinding	mechanically, on land	in-situ by wave actions, water movement
Risk of secondary mineral formation	high, due to saturation levels in pore fluids	low, due to dilution by ambient seawater
Background rain rate of	detrital minerals; high risk of fast alkaline mineral burial POC; high rates may enhance mineral dissolution	low impact
Risk of mineral relocation	medium, strong bottom currents may transport minerals to offshore depocenters	high, transport by wave action and currents out of turbulent zone

TA detection, challenged by	water depths - logistical difficulties	high dilution factors with seawater
	large seawater alkalinity background	turbulent waters, impacting stationary sensor systems
Air-sea exchange	enhanced by benthic-pelagic coupling	Instantaneous
	enhanced by currents, upwelling	

3.7.2 Considerations for best research practices

Quantity of deployed mineral: As the effects on the ecosystem by local alkalinity enhancement are still subject of current investigation, care should be taken when adding minerals to the seafloor. The risk of smothering flora, sessile organisms and clogging of burrows with mineral particles can be minimized by avoiding large deposits in the target area. It is currently unknown whether locally enhanced TA increases in sediment pore ~~waters-fluids~~ driven by oversupply of minerals might be detrimental to certain organisms or produce a shift in the microbial community, potentially affecting mineral dissolution rates. Therefore, dispersed mineral distribution is desirable by, for example, sprinkler systems. Post-deployment channelling of minerals to depocenters by bottom currents might be unavoidable for fine-grained particles. To avoid an accumulation of undissolved minerals on the seafloor, potentially negatively affecting marine ecosystems, care must be taken in assessing the quantity added. An upper limit of long-term mineral addition may be scaled to the local annual POC rain rate depending on the stoichiometry of CO₂ sequestration by the relevant mineral, if the CO₂ released from carbon respiration is quantitatively consumed by benthic weathering. This also assumes that mineral dissolution is tightly coupled to the remineralization of organic matter, which is unlikely to be universally the case. This question is currently being addressed in benthic mesocosm experiments (see Riebesell et al., 2023, this Guide) and still requires verification in field trials. For mafic minerals such as olivine, further unwanted side effects may arise due to release of heavy metals that may be toxic to marine organisms at higher concentrations (e.g., Ni). Testing the potential accumulation of metals in locally sourced sediment cores amended with minerals under laboratory conditions is recommended.

Secondary precipitates: The precipitation of secondary minerals either as discrete grains or on the surface of the added alkaline mineral, decreasing its effective surface area, will hamper the efficiency of CO₂ removal. ~~Especially in the case of secondary silicate precipitation, many unknowns remain concerning the controlling factors of formation. The conditions under which secondary mineral formation on the seafloor are favourable are mostly unknown.~~ Identification of reaction pathways and rates

will require highly precise monitoring ~~analyties~~ either of the solid or the fluid phase. Analyses of the fluid phase are challenged
940 ~~by due to~~ the large background seawater concentrations of chemical tracers, though distinct changes in pore fluid chemistry
(e.g. K, Li, Mg) and/or the application of stable isotope tracers (e.g. Si, B, Li, K) have the potential to identify secondary
mineral precipitation. Analyses of the solid phase can identify secondary minerals as well, either by bulk rock quantification
techniques (e.g. XRD), in-situ mineral analyses (e.g. EMP, NanoSIMS, laser-ablation MC-ICPMS) and/or sequential leaching
945 procedures; however, it remains a challenge to identify if the precipitates are of marine or terrestrial origin. For a reliable
quantification of secondary mineral formation in the context of OAE, repeated sampling of solid and fluid phases at regular
intervals needs to be conducted to assess element turnover and thus CO₂ sequestration.

Methods of detection: Arguably the biggest challenge is to quantify and monitor CO₂ sequestration related to mineral addition
on the seafloor. In low-energy deeper waters, the use of benthic chambers is an option to monitor the carbonate system over
950 discrete time intervals. However, artifacts such as changing redox conditions within the chamber due to oxygen depletion need
to be considered and if possible, compensated for in situ. Regular sampling is also needed. In the shallow and easily accessible
high-energy environment, regular water sampling is unlikely to detect alkalinity increase or CO₂ drawdown in this highly
diluted and well-mixed environment. Long-term monitoring using autonomous chemical sensor platforms for detection of
changes in pH, pCO₂ and TA (Sonnichsen et al., 2023) is an option, but highly challenging due to large fluctuations over
955 timescales ranging from hours to years. Keeping track of the mass of mineral gains over time may yield more robust results.

Conclusions

OAE as a potential solution to combat ocean acidification and remove CO₂ from the air continues to show great promise.
OAE's unique potential among CDR approaches to compensate for CO₂ degassing from the ocean resulting from large-scale
atmospheric CO₂ removal makes it an especially valuable approach worthy of continued pursuit. This chapter has delved into
960 technical aspects of the various technologies, and considerations for best practices in their research and development. Although
challenges remain, such as cost-effectiveness and minimizing environmental impacts, pilot projects have begun to demonstrate
the feasibility of deploying various OAE techniques in relevant operational environments. Continued innovation and
collaboration among scientists, engineers, and policymakers will be crucial in refining these technologies further. While initial
experiments have been successful on a smaller scale, significant challenges lie in deploying these techniques on a global level.
965 Addressing logistical complexities, ensuring proper monitoring and regulation, and securing necessary funding are imperative
for successful scaling. Additionally, considering regional variations and selecting appropriate sites for implementation will be
vital for maximizing the efficiency and effectiveness of OAE projects. The identification and implementation of best practices
are essential for the success of OAE initiatives. Conducting comprehensive environmental impact assessments, employing
adaptive management strategies, and promoting transparency and public engagement are crucial steps in ensuring responsible
970 deployment. Learning from past experiences, both positive and negative, will help refine the methodologies and minimize any

unintended consequences. It is crucial to approach this strategy with careful consideration, ensuring technology readiness, addressing scaling challenges, and implementing best practices.

[3.8 Recommendations for research on technical aspects of OAE standards and guidelines](#)

- [OAE shows promise as a potential CDR solution, and pilot projects and research activities have begun to demonstrate its feasibility in relevant environments. Continued collaboration among scientists, engineers, and policymakers will be crucial in optimizing these technologies. To maximize the effectiveness of OAE, it is critical to consider location or regional specific constraints to select appropriate application sites for specific OAE approaches.](#)
- [Conducting comprehensive environmental impact assessments, employing adaptive management strategies, and promoting transparency and public engagement are crucial steps in ensuring responsible deployment of OAE.](#)
- [Excessive accumulation of undissolved minerals on the seafloor, potentially harming marine organisms, should be avoided; assuming that benthic mineral dissolution is coupled to organic matter remineralization, the POC rain rate can be used as an upper limit of the amount of mineral addition.](#)
- [The potential formation of secondary minerals, either carbonates or silicates, which can reduce the net CO₂-sequestration efficiency of an ~~Ocean Alkalinity Enhancement~~OAE approach, needs to be monitored on a regular basis by thorough chemical analyses of the involved fluid and/or solid phases.](#)
- [Technology Readiness Levels for the different ~~Ocean Alkalinity Enhancement~~OAE measures need to be increased in laboratory experiments and in field studies, also to identify potential 'tipping points' for organism viability and the ecosystem in general.](#)

Appendices

Definitions and common abbreviations

AWL – accelerated weathering of limestone

CDR – carbon dioxide removal

CCS – carbon capture and storage, specifically where CO₂ is concentrated from waste streams

DIC – total dissolved inorganic carbon

OAE – ocean alkalinity enhancement

Ω_{cal} – calcium carbonate (calcite) saturation state

pCO₂ – partial pressure of CO_{2g}

pH – negative logarithm of the hydrogen ion activity, a measure of acidity

TA – total alkalinity, the capacity of a solution to neutralize acid

Author Contributions

1005 MDE, SG, and PR scoped and edited the contents of the chapter. MDE contributed to section 3.2, SG contributed to section 3.7, PR contributed to sections 3.4 and 3.5, LB contributed to section 3.5, JC contributed to section 3.1 and the conclusions, AD contributed to section 3.7, SF contributed to sections 3.1 and 3.4, PG contributed to section 3.7, OH contributed to section 3.4, CRL contributed to section 3.6, GHR contributed to section 3.2 and 3.3, JR contributed to section 3.6.

Competing Interests

1010 MDE is Co-Founder and Chief Scientific Advisor to Ebb Carbon, Inc. GHR is Co-founder and Chief Technology Officer at Planetary Technologies, Inc. OH is a Research and Development Scientist for Origen Carbon Solutions.

Acknowledgements

1015 PR acknowledges funding from the European Union's Horizon 2020 Research and Innovation Program under grant 869357 (project OceanNETs: Ocean-based Negative Emission Technologies analyzing the feasibility, risks, and co-benefits of ocean-based negative emission technologies for stabilizing the climate), and philanthropic funding from the ClimateWorks Foundation and Climate Pathfinders Foundation. MDE acknowledges funding from the Grantham Foundation for the Protection of the Environment. SG acknowledges funding from the German Federal Ministry of Education and Research (Grant No 03F0895) Project RETAKE, DAM Mission "Marine carbon sinks in decarbonization pathways" (CDRmare).

1020 This is a contribution to the "Guide for Best Practices on Ocean Alkalinity Enhancement Research". We thank our funders the ClimateWorks Foundation and the Prince Albert II of Monaco Foundation. Thanks are also due to the Villefranche Oceanographic Laboratory for supporting the lead authors' meeting in January 2023.

References

1025 Anderson, R.F., Rowe, G.T., Kemp, P.F., Trumbore, S., Biscaye, P.E., 1994. Carbon budget for the mid-slope depocenter of the Middle Atlantic Bight. *Deep Sea Research Part II: Topical Studies in Oceanography* 41, 669–703. [https://doi.org/10.1016/0967-0645\(94\)90040-X](https://doi.org/10.1016/0967-0645(94)90040-X)

Bach, L.T., Gill, S.J., Rickaby, R.E.M., Gore, S., Renforth, P., 2019. CO2 Removal With Enhanced Weathering and Ocean Alkalinity Enhancement: Potential Risks and Co-benefits for Marine Pelagic Ecosystems. *Front. Clim.* 1, 7. <https://doi.org/10.3389/fclim.2019.00007>

- 1030 Bange, H.W., 2006a. New Directions: The importance of oceanic nitrous oxide emissions. *Atmospheric Environment* 40, 198–199. <https://doi.org/10.1016/j.atmosenv.2005.09.030>
- Bange, H.W., 2006b. Nitrous oxide and methane in European coastal waters. *Estuarine, Coastal and Shelf Science* 70, 361–374. <https://doi.org/10.1016/j.ecss.2006.05.042>
- Beerling, D.J., 2017. Enhanced rock weathering: biological climate change mitigation with co-benefits for food security? *Biol. Lett.* 13, 20170149. <https://doi.org/10.1098/rsbl.2017.0149>
- 1035 Bischoff, J.L., Fitzpatrick, J.A., Rosenbauer, R.J., 1993. The Solubility and Stabilization of Ikaite ($\text{CaCO}_3 \cdot 6\text{H}_2\text{O}$) from 0° to 25°C: Environmental and Paleoclimatic Implications for Thinolite Tufa. *The Journal of Geology* 101, 21–33. <https://doi.org/10.1086/648194>
- Bots, P., Benning, L.G., Rodriguez-Blanco, J.-D., Roncal-Herrero, T., Shaw, S., 2012. Mechanistic Insights into the
1040 Crystallization of Amorphous Calcium Carbonate (ACC). *Crystal Growth & Design* 12, 3806–3814. <https://doi.org/10.1021/cg300676b>
- Boyd, P.W., Watson, A.J., Law, C.S., Abraham, E.R., Trull, T., Murdoch, R., Bakker, D.C.E., Bowie, A.R., Buesseler, K.O., Chang, H., Charette, M., Croot, P., Downing, K., Frew, R., Gall, M., Hadfield, M., Hall, J., Harvey, M., Jameson, G., LaRoche, J., Liddicoat, M., Ling, R., Maldonado, M.T., McKay, R.M., Nodder, S., Pickmere, S., Pridmore, R., Rintoul, S., Safi, K., Sutton, P., Strzepek, R., Tanneberger, K., Turner, S., Waite, A., Zeldis, J., 2000. A mesoscale phytoplankton
1045 bloom in the polar Southern Ocean stimulated by iron fertilization. *Nature* 407, 695–702. <https://doi.org/10.1038/35037500>
- Bre\vcević, L., Nielsen, A.E., Oskarsson, Å., Hewitt, G.M., Kutney, J.P., Li, K., Milanova, R.K., Nakata, H., Nasiri, A., Okada, Y., 1993. Solubility of calcium carbonate hexahydrate. *Acta Chemica Scandinavica* 47, 668–673. <https://doi.org/10.3891/acta.chem.scand.47-0668>
- 1050 Brooks, R., Clark, L. m., Thurston, E.F., Freeth, F.A., 1997. Calcium carbonate and its hydrates. *Philosophical Transactions of the Royal Society of London. Series A, Mathematical and Physical Sciences* 243, 145–167. <https://doi.org/10.1098/rsta.1950.0016>
- Cadée, G.C., 1976. Sediment reworking by arenicola marina on tidal flats in the Dutch Wadden Sea. *Netherlands Journal of Sea Research* 10, 440–460. [https://doi.org/10.1016/0077-7579\(76\)90020-X](https://doi.org/10.1016/0077-7579(76)90020-X)
- 1055 Caldeira, K., Rau, G.H., 2000. Accelerating carbonate dissolution to sequester carbon dioxide in the ocean: Geochemical implications. *Geophys. Res. Lett.* 27, 225–228. <https://doi.org/10.1029/1999GL002364>
- Caserini, S., Barreto, B., Lanfredi, C., Cappello, G., Ross Morrey, D., Grosso, M., 2019. Affordable CO2 negative emission through hydrogen from biomass, ocean liming, and CO2 storage. *Mitig Adapt Strateg Glob Change* 24, 1231–1248. <https://doi.org/10.1007/s11027-018-9835-7>
- 1060 Caserini, S., Cappello, G., Righi, D., Raos, G., Campo, F., De Marco, S., Renforth, P., Varliero, S., Grosso, M., 2021a. Buffered accelerated weathering of limestone for storing CO2: Chemical background. *International Journal of Greenhouse Gas Control* 112, 103517. <https://doi.org/10.1016/j.ijggc.2021.103517>

- Caserini, S., Pagano, D., Campo, F., Abbà, A., De Marco, S., Righi, D., Renforth, P., Grosso, M., 2021b. Potential of Maritime Transport for Ocean Liming and Atmospheric CO₂ Removal. *Front. Clim.* 3, 575900. <https://doi.org/10.3389/fclim.2021.575900>
- 1065 Chou, W.-C., Gong, G.-C., Hsieh, P.-S., Chang, M.-H., Chen, H.-Y., Yang, C.-Y., Syu, R.-W., 2015. Potential impacts of effluent from accelerated weathering of limestone on seawater carbon chemistry: A case study for the Hoping power plant in northeastern Taiwan. *Marine Chemistry* 168, 27–36. <https://doi.org/10.1016/j.marchem.2014.10.008>
- Committee on A Research Strategy for Ocean-based Carbon Dioxide Removal and Sequestration, Ocean Studies Board, Division on Earth and Life Studies, National Academies of Sciences, Engineering, and Medicine, 2022. A Research Strategy for Ocean-based Carbon Dioxide Removal and Sequestration. National Academies Press, Washington, D.C. <https://doi.org/10.17226/26278>
- 1070 Cooney, G., 2022. BEST PRACTICES FOR LIFE CYCLE ASSESSMENT (LCA) OF DIRECT AIR CAPTURE WITH STORAGE (DACs).
- Cyronak, T., Albright, R., and Bach, L.: Field experiments in ocean alkalinity enhancement research, *State Planet Discuss.* [preprint], <https://doi.org/10.5194/sp-2023-9>, in review, 2023.
- Dale, A.W., Sommer, S., Lomnitz, U., Montes, I., Treude, T., Liebetrau, V., Gier, J., Hensen, C., Dengler, M., Stolpovsky, K., Bryant, L.D., Wallmann, K., 2015. Organic carbon production, mineralisation and preservation on the Peruvian margin. *Biogeosciences* 12, 1537–1559. <https://doi.org/10.5194/bg-12-1537-2015>
- 1080 Davies, P.J., Bubela, B., 1973. The transformation of nesquehonite into hydromagnesite. *Chemical Geology* 12, 289–300. [https://doi.org/10.1016/0009-2541\(73\)90006-5](https://doi.org/10.1016/0009-2541(73)90006-5)
- de Lannoy, C.-F., Eisaman, M.D., Jose, A., Karnitz, S.D., DeVaul, R.W., Hannun, K., Rivest, J.L.B., 2018. Indirect ocean capture of atmospheric CO₂: Part I. Prototype of a negative emissions technology. *International Journal of Greenhouse Gas Control* 70, 243–253. <https://doi.org/10.1016/j.ijggc.2017.10.007>
- 1085 Doelman, C.J., Leurs, R., Oosterom, W. C., Bast, A.: Mineral dust exposure and free radical-mediated lung damage. *Exp Lung*
- Eisaman, M.D., 2020. Negative Emissions Technologies: The Tradeoffs of Air-Capture Economics. *Joule* 4, 516–520. <https://doi.org/10.1016/j.joule.2020.02.007>
- Eisaman, M. D., Parajuly, K., Tuganov, A., Eldershaw, C., Chang, N., and Littau, K. A.: CO₂ extraction from seawater using bipolar membrane electrodialysis, *Energy Environ. Sci.*, 5, 7346, <https://doi.org/10.1039/c2ee03393c>, 2012.
- 1090 Eisaman, M.D., Rivest, J.L.B., Karnitz, S.D., de Lannoy, C.-F., Jose, A., DeVaul, R.W., Hannun, K., 2018. Indirect ocean capture of atmospheric CO₂: Part II. Understanding the cost of negative emissions. *International Journal of Greenhouse Gas Control* 70, 254–261. <https://doi.org/10.1016/j.ijggc.2018.02.020>
- European Commission. Joint Research Centre. Institute for Prospective Technological Studies., 2013. Best available techniques (BAT) reference document for the production of cement, lime and magnesium oxide: Industrial Emissions Directive 2010/75/EU (integrated pollution prevention and control). Publications Office, LU.
- 1095

- European Commission, Commission Decision (EU) 2017/ 848 - of 17 May 2017 - laying down criteria and methodological standards on good environmental status of marine waters and specifications and standardised methods for monitoring and assessment, and repealing Decision 2010/ 477/ EU, 2017.
- 1100 Fakhraee, M., Li, Z., Planavsky, N.J., Reinhard, C.T., 2023. A biogeochemical model of mineral-based ocean alkalinity enhancement: impacts on the biological pump and ocean carbon uptake. *Environ. Res. Lett.* 18, 044047. <https://doi.org/10.1088/1748-9326/acc9d4>
- FISCHER, H.C., 1955. Calcination of Calcite: I, Effect of Heating Rate and Temperature on Bulk Density of Calcium Oxide. *Journal of the American Ceramic Society* 38, 245–251. <https://doi.org/10.1111/j.1151-2916.1955.tb14939.x>
- 1105 Flipkens, G., Blust, R., Town, R.M., 2021. Deriving Nickel (Ni(II)) and Chromium (Cr(III)) Based Environmentally Safe Olivine Guidelines for Coastal Enhanced Silicate Weathering. *Environ. Sci. Technol.* 55, 12362–12371. <https://doi.org/10.1021/acs.est.1c02974>
- Foteinis, S., Andresen, J., Campo, F., Caserini, S., Renforth, P., 2022. Life cycle assessment of ocean liming for carbon dioxide removal from the atmosphere. *Journal of Cleaner Production* 370, 133309. <https://doi.org/10.1016/j.jclepro.2022.133309>
- 1110 Foteinis, S., Campbell, J.S., Renforth, P., 2023. Life Cycle Assessment of Coastal Enhanced Weathering for Carbon Dioxide Removal from Air. *Environ. Sci. Technol.* 57, 6169–6178. <https://doi.org/10.1021/acs.est.2c08633>
- Fuhr, M., Geilert, S., Schmidt, M., Wallmann, K., 2021. Kinetics of olivine weathering in seawater: an experimental study, in: Goldschmidt2021 Abstracts. Presented at the Goldschmidt2021, European Association of Geochemistry, Virtual. <https://doi.org/10.7185/gold2021.7375>
- 1115 Garai, P., Banerjee, P., Mondal, P., Saha, N.C., 2021. Effect of Heavy Metals on Fishes: Toxicity and Bioaccumulation 11. Gartner, E., 2018. Discussion of the paper “A new view on the kinetics of tricalcium silicate hydration,” by L. Nicoleau and A. Nonat, *Cem. Concr. Res.* 86 (2016) 1–11. *Cement and Concrete Research* 104, 114–117. <https://doi.org/10.1016/j.cemconres.2017.10.015>
- Gattuso, J.-P., Frankignoulle, M., Wollast, R., 1998. CARBON AND CARBONATE METABOLISM IN COASTAL AQUATIC ECOSYSTEMS. *Annu. Rev. Ecol. Syst.* 29, 405–434. <https://doi.org/10.1146/annurev.ecolsys.29.1.405>
- 1120 Geilert, S., Frick, D.A., Garbe-Schönberg, D., Scholz, F., Sommer, S., Grasse, P., Vogt, C., Dale, A.W., 2023. Coastal El Niño triggers rapid marine silicate alteration on the seafloor. *Nat Commun* 14, 1676. <https://doi.org/10.1038/s41467-023-37186-5>
- Glass, J.B., Dupont, C.L., 2017. Oceanic Nickel Biogeochemistry and the Evolution of Nickel Use, in: Zamble, D., Rowińska-Żyrek, M., Kozłowski, H. (Eds.), *The Biological Chemistry of Nickel*. The Royal Society of Chemistry, pp. 12–26.
- 1125 Gore, S., Renforth, P., Perkins, R., 2019. The potential environmental response to increasing ocean alkalinity for negative emissions. *Mitig Adapt Strateg Glob Change* 24, 1191–1211. <https://doi.org/10.1007/s11027-018-9830-z>
- Greiner, J., Derkachev, A., 2004. Glendonites and methane-derived Mg-calcites in the Sea of Okhotsk, Eastern Siberia: implications of a venting-related ikaite/glendonite formation. *Marine Geology* 204, 129–144. [https://doi.org/10.1016/S0025-3227\(03\)00354-2](https://doi.org/10.1016/S0025-3227(03)00354-2)

- 1130 Guo, J.A., Strzepak, R., Willis, A., Ferderer, A., Bach, L.T., 2022. Investigating the effect of nickel concentration on phytoplankton growth to assess potential side-effects of ocean alkalinity enhancement. *Biogeosciences* 19, 3683–3697. <https://doi.org/10.5194/bg-19-3683-2022>
- Guy, C., Schott, J., 1989. Multisite surface reaction versus transport control during the hydrolysis of a complex oxide. *Chemical Geology* 78, 181–204. [https://doi.org/10.1016/0009-2541\(89\)90057-0](https://doi.org/10.1016/0009-2541(89)90057-0)
- 1135 Hamilton, J.L., Wilson, S.A., Morgan, B., Harrison, A.L., Turvey, C.C., Paterson, D.J., Dipple, G.M., Southam, G., 2020. Accelerating Mineral Carbonation in Ultramafic Mine Tailings via Direct CO₂ Reaction and Heap Leaching with Potential for Base Metal Enrichment and Recovery. *Economic Geology* 115, 303–323. <https://doi.org/10.5382/econgeo.4710>
- Hangx, S.J.T., Spiers, C.J., 2009. Coastal spreading of olivine to control atmospheric CO₂ concentrations: A critical analysis of viability. *International Journal of Greenhouse Gas Control* 3, 757–767. <https://doi.org/10.1016/j.ijggc.2009.07.001>
- 1140 Hartmann, J., Jansen, N., Dürr, H.H., Kempe, S., Köhler, P., 2009. Global CO₂-consumption by chemical weathering: What is the contribution of highly active weathering regions? *Global and Planetary Change* 69, 185–194. <https://doi.org/10.1016/j.gloplacha.2009.07.007>
- Hartmann, J., Moosdorf, N., 2012. The new global lithological map database GLiM: A representation of rock properties at the Earth surface: TECHNICAL BRIEF. *Geochem. Geophys. Geosyst.* 13. <https://doi.org/10.1029/2012GC004370>
- 1145 Hartmann, J., Suitner, N., Lim, C., Schneider, J., Marín-Samper, L., Arístegui, J., Renforth, P., Taucher, J., Riebesell, U., 2023. Stability of alkalinity in ocean alkalinity enhancement (OAE) approaches – consequences for durability of CO₂ storage. *Biogeosciences* 20, 781–802. <https://doi.org/10.5194/bg-20-781-2023>
- Harvey, L.D.D., 2008. Mitigating the atmospheric CO₂ increase and ocean acidification by adding limestone powder to upwelling regions. *J. Geophys. Res.* 113, C04028. <https://doi.org/10.1029/2007JC004373>
- 1150 Hauck, J., Köhler, P., Wolf-Gladrow, D., Völker, C., 2016. Iron fertilisation and century-scale effects of open ocean dissolution of olivine in a simulated CO₂ removal experiment. *Environ. Res. Lett.* 11, 024007. <https://doi.org/10.1088/1748-9326/11/2/024007>
- He, J., Tyka, M.D., 2023. Limits and CO₂ equilibration of near-coast alkalinity enhancement. *Biogeosciences* 20, 27–43. <https://doi.org/10.5194/bg-20-27-2023>
- 1155 Hinga, K., 2002. Effects of pH on coastal marine phytoplankton. *Mar. Ecol. Prog. Ser.* 238, 281–300. <https://doi.org/10.3354/meps238281>
- Ho, D. T., Bopp, L., Palter, J. B., Long, M. C., Boyd, P., Neukermans, G., and Bach, L.: Monitoring, Reporting, and Verification for Ocean Alkalinity Enhancement, *State Planet Discuss.* [preprint], <https://doi.org/10.5194/sp-2023-2>, in review, 2023.
- 1160 House, K.Z., House, C.H., Schrag, D.P., Aziz, M.J., 2007. Electrochemical Acceleration of Chemical Weathering as an Energetically Feasible Approach to Mitigating Anthropogenic Climate Change. *Environ. Sci. Technol.* 41, 8464–8470. <https://doi.org/10.1021/es0701816>

- Hu, Y.-B., Wolf-Gladrow, D.A., Dieckmann, G.S., Völker, C., Nehrke, G., 2014. A laboratory study of ikaite ($\text{CaCO}_3 \cdot 6\text{H}_2\text{O}$) precipitation as a function of pH, salinity, temperature and phosphate concentration. *Marine Chemistry* 162, 10–18.
1165 <https://doi.org/10.1016/j.marchem.2014.02.003>
- Ilyina, T., Wolf-Gladrow, D., Munhoven, G., Heinze, C., 2013. Assessing the potential of calcium-based artificial ocean alkalization to mitigate rising atmospheric CO_2 and ocean acidification: MODELING MITIGATION POTENTIAL OF AOA. *Geophys. Res. Lett.* 40, 5909–5914. <https://doi.org/10.1002/2013GL057981>
- ISO, 2006. Environmental management — Life cycle assessment — Principles and framework.
- 1170 Jahnke, R.A., Jahnke, D.B., 2000. Rates of C, N, P and Si recycling and denitri"cation at the US Mid-Atlantic continental slope depocenter.
- Jeandel, C., Oelkers, E.H., 2015. The influence of terrigenous particulate material dissolution on ocean chemistry and global element cycles. *Chemical Geology* 395, 50–66. <https://doi.org/10.1016/j.chemgeo.2014.12.001>
- Jeandel, C., Peucker-Ehrenbrink, B., Jones, M.T., Pearce, C.R., Oelkers, E.H., Godderis, Y., Lacan, F., Aumont, O., Arsouze, T., 2011. Ocean margins: The missing term in oceanic element budgets? *Eos Trans. AGU* 92, 217–218.
1175 <https://doi.org/10.1029/2011EO260001>
- Kazakov, A.V., Tikhomirova, M.M., Plotnikova, V.I., 1959. THE SYSTEM OF CARBONATE EQUILIBRIA. *International Geology Review* 1, 1–39. <https://doi.org/10.1080/00206815909473450>
- Kelland, M. et al. Metallurgy and Materials Society of CIM (Ed.): Proceedings of the 61st Conference of Metallurgists, COM 2022, Springer International Publishing, Cham, <https://doi.org/10.1007/978-3-031-17425-4>, 2023.
- 1180 Khesghi, H.S., 1995. Sequestering atmospheric carbon dioxide by increasing ocean alkalinity. *Energy* 20, 915–922. [https://doi.org/10.1016/0360-5442\(95\)00035-F](https://doi.org/10.1016/0360-5442(95)00035-F)
- Kim, S., Nitzsche, M.P., Rufer, S.B., Lake, J.R., Varanasi, K.K., Hatton, T.A., 2023. Asymmetric chloride-mediated electrochemical process for CO_2 removal from oceanwater. *Energy Environ. Sci.* 16, 2030–2044.
1185 <https://doi.org/10.1039/D2EE03804H>
- Kim, Y., Caumon, M.-C., Barres, O., Sall, A., Cauzid, J., 2021. Identification and composition of carbonate minerals of the calcite structure by Raman and infrared spectroscopies using portable devices. *Spectrochimica Acta Part A: Molecular and Biomolecular Spectroscopy* 261, 119980. <https://doi.org/10.1016/j.saa.2021.119980>
- Kirchner, J.S., Berry, A., Ohnemüller, F., Schnetger, B., Erich, E., Brumsack, H.-J., Lettmann, K.A., 2020a. Reducing CO_2 Emissions of a Coal-Fired Power Plant via Accelerated Weathering of Limestone: Carbon Capture Efficiency and Environmental Safety. *Environ. Sci. Technol.* 54, 4528–4535. <https://doi.org/10.1021/acs.est.9b07009>
- 1190 Kirchner, J.S., Lettmann, K.A., Schnetger, B., Wolff, J.-O., Brumsack, H.-J., 2020b. Carbon capture via accelerated weathering of limestone: Modeling local impacts on the carbonate chemistry of the southern North Sea. *International Journal of Greenhouse Gas Control* 92, 102855. <https://doi.org/10.1016/j.ijggc.2019.102855>

- 1195 Köhler, P., Abrams, J.F., Völker, C., Hauck, J., Wolf-Gladrow, D.A., 2013. Geoenvironmental impact of open ocean dissolution of olivine on atmospheric CO₂, surface ocean pH and marine biology. *Environ. Res. Lett.* 8, 014009. <https://doi.org/10.1088/1748-9326/8/1/014009>
- Königsberger, E., Königsberger, L.-C., Gamsjäger, H., 1999. Low-temperature thermodynamic model for the system Na₂CO₃-MgCO₃-CaCO₃-H₂O. *Geochimica et Cosmochimica Acta* 63, 3105–3119. [https://doi.org/10.1016/S0016-7037\(99\)00238-0](https://doi.org/10.1016/S0016-7037(99)00238-0)
- 1200 Kumar, A., Du, F., Lienhard, J.H., 2021. Caustic Soda Production, Energy Efficiency, and Electrolyzers. *ACS Energy Lett.* 6, 3563–3566. <https://doi.org/10.1021/acseenergylett.1c01827>
- Lammers, L. N., Duan, Y., Anaya, L., Koishi, A., Lopez, R., Delima, R., Jassby, D., and Sedlak, D. L.: Electrolytic Sulfuric Acid Production with Carbon Mineralization for Permanent Carbon Dioxide Removal, *ACS Sustainable Chem. Eng.*, 11, 1205 4800–4812, <https://doi.org/10.1021/acssuschemeng.2c07441>, 2023.
- Langer, W. H., San Juan, C. A., Rau, G. H. and Caldeira, K.: Accelerated weathering of limestone for CO₂ mitigation: Opportunities for the stone and cement industries, *Mining Eng.* 61, 27–32, https://www.researchgate.net/publication/283868780_Accelerated_weathering_of_limestone_for_CO2_mitigation_Opportunities_for_the_stone_and_cement_industries#fullTextFileContent, 2009.
- 1210 La Plante, E.C., Simonetti, D.A., Wang, J., Al-Turki, A., Chen, X., Jassby, D., Sant, G.N., 2021. Saline Water-Based Mineralization Pathway for Gigatonne-Scale CO₂ Management. *ACS Sustainable Chem. Eng.* 9, 1073–1089. <https://doi.org/10.1021/acssuschemeng.0c08561>
- La Plante, E. C., Chen, X., Bustillos, S., Bouissonnie, A., Traynor, T., Jassby, D., Corsini, L., Simonetti, D. A., and Sant, G. N., 2023. Electrolytic Seawater Mineralization and the Mass Balances That Demonstrate Carbon Dioxide Removal, *ACS EST Eng.*, 3, 955–968, <https://doi.org/10.1021/acsesteng.3c00004>
- 1215 Lammers, L.N., Duan, Y., Anaya, L., Koishi, A., Lopez, R., Delima, R., Jassby, D., Sedlak, D.L., 2023. Electrolytic Sulfuric Acid Production with Carbon Mineralization for Permanent Carbon Dioxide Removal. *ACS Sustainable Chem. Eng.* 11, 4800–4812. <https://doi.org/10.1021/acssuschemeng.2c07441>
- Laruelle, G.G., Cai, W.-J., Hu, X., Gruber, N., Mackenzie, F.T., Regnier, P., 2018. Continental shelves as a variable but 1220 increasing global sink for atmospheric carbon dioxide. *Nat Commun* 9, 454. <https://doi.org/10.1038/s41467-017-02738-z>
- Laruelle, G.G., Lauerwald, R., Pfeil, B., Regnier, P., 2014. Regionalized global budget of the CO₂ exchange at the air-water interface in continental shelf seas: Continental shelf seas CO₂ fluxes. *Global Biogeochem. Cycles* 28, 1199–1214. <https://doi.org/10.1002/2014GB004832>
- Lennie, A.R., Tang, C.C., Thompson, S.P., 2004. The structure and thermal expansion behaviour of ikaite, CaCO₃·6H₂O, 1225 from T = 114 to T = 293 K. *Mineralogical Magazine* 68, 135–146. <https://doi.org/10.1180/0026461046810176>
- Linke, P., Suess, E., Torres, M., Martens, V., Rugh, W.D., Ziebis, W., Kulm, L.D., 1994. In situ measurement of fluid flow from cold seeps at active continental margins. *Deep Sea Research Part I: Oceanographic Research Papers* 41, 721–739. [https://doi.org/10.1016/0967-0637\(94\)90051-5](https://doi.org/10.1016/0967-0637(94)90051-5)

- Little, C. D. et al. Electrochemical apparatus to generate hydrogen and sequester carbon dioxide, US Patent 8,227,127 B2, July 24, 2012.
- 1230 Longhurst, A., Sathyendranath, S., Platt, T., & Caverhill, C. (1995). An estimate of global primary production in the ocean from satellite radiometer data. *Journal of Plankton Research*, 17(6), 1245–1271. <https://doi.org/10.1093/plankt/17.6.1245>
- Madeddu, S., Priestnall, M., Godoy, E., Kumar, R.V., Raymahasay, S., Evans, M., Wang, R., Manenye, S., Kinoshita, H., 2015. Extraction of Mg(OH)₂ from Mg silicate minerals with NaOH assisted with H₂O: implications for CO₂ capture from exhaust flue gas. *Faraday Discuss.* 183, 369–387. <https://doi.org/10.1039/C5FD00047E>
- 1235 Marion, G.M., 2001. Carbonate mineral solubility at low temperatures in the Na-K-Mg-Ca-H-Cl-SO₄-OH-HCO₃-CO₃-CO₂-H₂O system. *Geochimica et Cosmochimica Acta* 65, 1883–1896. [https://doi.org/10.1016/S0016-7037\(00\)00588-3](https://doi.org/10.1016/S0016-7037(00)00588-3)
- Marland, G., 1975. Phase equilibria in the system calcium carbonate-water. *Geochimica et Cosmochimica Acta* 39, 1193–1197. [https://doi.org/10.1016/0016-7037\(75\)90061-7](https://doi.org/10.1016/0016-7037(75)90061-7)
- 1240 McLaren, D., 2012. A comparative global assessment of potential negative emissions technologies. *Process Safety and Environmental Protection* 90, 489–500. <https://doi.org/10.1016/j.psep.2012.10.005>
- McNeil, B.I., Matear, R.J., Key, R.M., Bullister, J.L., Sarmiento, J.L., 2003. Anthropogenic CO₂ Uptake by the Ocean Based on the Global Chlorofluorocarbon Data Set. *Science* 299, 235–239. <https://doi.org/10.1126/science.1077429>
- McQueen, N., Kelemen, P., Dipple, G., Renforth, P., Wilcox, J., 2020. Ambient weathering of magnesium oxide for CO₂ removal from air. *Nat Commun* 11, 3299. <https://doi.org/10.1038/s41467-020-16510-3>
- 1245 Meysman, F.J.R., Cornelissen, R., Trashin, S., Bonn , R., Martinez, S.H., Van Der Veen, J., Blom, C.J., Karman, C., Hou, J.-L., Eachambadi, R.T., Geelhoed, J.S., Wael, K.D., Beaumont, H.J.E., Cleuren, B., Valcke, R., Van Der Zant, H.S.J., Boschker, H.T.S., Manca, J.V., 2019. A highly conductive fibre network enables centimetre-scale electron transport in multicellular cable bacteria. *Nat Commun* 10, 4120. <https://doi.org/10.1038/s41467-019-12115-7>
- 1250 Meysman, F.J.R., Montserrat, F., 2017. Negative CO₂ emissions via enhanced silicate weathering in coastal environments. *Biol. Lett.* 13, 20160905. <https://doi.org/10.1098/rsbl.2016.0905>
- Mikkelsen, A., Andersen, A.B., Engelsen, S.B., Hansen, H.C.B., Larsen, O., Skibsted, L.H., 1999. Presence and Dehydration of Ikaite, Calcium Carbonate Hexahydrate, in Frozen Shrimp Shell. *J. Agric. Food Chem.* 47, 911–917. <https://doi.org/10.1021/jf980932a>
- 1255 Montserrat, F., Renforth, P., Hartmann, J., Leermakers, M., Knops, P., Meysman, F.J.R., 2017. Olivine Dissolution in Seawater: Implications for CO₂ Sequestration through Enhanced Weathering in Coastal Environments. *Environ. Sci. Technol.* 51, 3960–3972. <https://doi.org/10.1021/acs.est.6b05942>
- Moras, C.A., Bach, L.T., Cyronak, T., Joannes-Boyau, R., Schulz, K.G., 2022. Ocean alkalinity enhancement – avoiding runaway CaCO₃ precipitation during quick and hydrated lime dissolution. *Biogeosciences* 19, 3537–3557. <https://doi.org/10.5194/bg-19-3537-2022>
- 1260

- Moropoulou, A., Bakolas, A., Aggelakopoulou, E., 2001. The Effects of Limestone Characteristics and Calcination Temperature on the Reactivity of Quicklime. *Cement and Concrete Research* 31, 633–639. [https://doi.org/10.1016/S0008-8846\(00\)00490-7](https://doi.org/10.1016/S0008-8846(00)00490-7)
- 1265 Nduagu, E., Björklöf, T., Fagerlund, J., Wärnå, J., Geerlings, H., Zevenhoven, R., 2012. Production of magnesium hydroxide from magnesium silicate for the purpose of CO₂ mineralisation – Part 1: Application to Finnish serpentinite. *Minerals Engineering* 30, 75–86. <https://doi.org/10.1016/j.mineng.2011.12.004>
- Neumann, A., Van Beusekom, J.E.E., Eisele, A., Emeis, K., Friedrich, J., Kröncke, I., Logemann, E.L., Meyer, J., Naderipour, C., Schüchel, U., Wrede, A., Zettler, M.L., 2021. Macrofauna as a major driver of benthic-pelagic exchange in the southern North Sea. *Limnology & Oceanography* 66, 2203–2217. <https://doi.org/10.1002/lno.11748>
- 1270 Nishiyama, R., Munemoto, T., Fukushi, K., 2013. Formation condition of monohydrocalcite from CaCl₂–MgCl₂–Na₂CO₃ solutions. *Geochimica et Cosmochimica Acta* 100, 217–231. <https://doi.org/10.1016/j.gca.2012.09.002>
- O'Brien, T., Bommaraju, T.V., Hine, F., 2005. *Handbook of chlor-alkali technology*. Springer, New York.
- Oelkers, E.H., Declercq, J., Saldi, G.D., Gislason, S.R., Schott, J., 2018. Olivine dissolution rates: A critical review. *Chemical Geology* 500, 1–19. <https://doi.org/10.1016/j.chemgeo.2018.10.008>
- 1275 Orr, J.C., Fabry, V.J., Aumont, O., Bopp, L., Doney, S.C., Feely, R.A., Gnanadesikan, A., Gruber, N., Ishida, A., Joos, F., Key, R.M., Lindsay, K., Maier-Reimer, E., Matear, R., Monfray, P., Mouchet, A., Najjar, R.G., Plattner, G.-K., Rodgers, K.B., Sabine, C.L., Sarmiento, J.L., Schlitzer, R., Slater, R.D., Totterdell, I.J., Weirig, M.-F., Yamanaka, Y., Yool, A., 2005. Anthropogenic ocean acidification over the twenty-first century and its impact on calcifying organisms. *Nature* 437, 681–686. <https://doi.org/10.1038/nature04095>
- 1280 Oskierski, H.C., Turvey, C.C., Wilson, S., Dlugogorski, B.Z., Altarawneh, M., Mavromatis, V., 2021. Mineralisation of atmospheric CO₂ in hydromagnesite in ultramafic mine tailings – Insights from Mg isotopes. *Geochimica et Cosmochimica Acta* 309, 191–208. <https://doi.org/10.1016/j.gca.2021.06.020>
- Pan, X.-J., Dou, Z.-H., Zhang, T.-A., Meng, D.-L., Fan, Y.-Y., 2020. Separation of metal ions and resource utilization of magnesium from saline lake brine by membrane electrolysis. *Separation and Purification Technology* 251, 117316. <https://doi.org/10.1016/j.seppur.2020.117316>
- 1285 Papadimitriou, S., Kennedy, H., Kennedy, P., Thomas, D.N., 2014. Kinetics of ikaite precipitation and dissolution in seawater-derived brines at sub-zero temperatures to 265 K. *Geochimica et Cosmochimica Acta* 140, 199–211. <https://doi.org/10.1016/j.gca.2014.05.031>
- Pedersen, F. M. & Hansen, P.: Effects of high pH on natural planktonic community. *Marine Ecology-progress Series - MEPS*. 1290 260. 19-31. <https://doi.org/10.3354/meps260019>. 2003.
- Penman, D.E., Rooney, A.D., 2019. Coupled carbon and silica cycle perturbations during the Marinoan snowball Earth deglaciation. *Geology* 47, 317–320. <https://doi.org/10.1130/G45812.1>

- Pesce, C., Godina, M.C., Henry, A., Pesce, G.L., 2023. Effects of Steam-Slaking on the Characteristics of Lime from Three Different UK Manufacturers, in: Escalante-Garcia, J.I., Castro Borges, P., Duran-Herrera, A. (Eds.), Proceedings of the 75th RILEM Annual Week 2021. Springer International Publishing, Cham, pp. 771–780.
- 1295 Petit, J.R., Jouzel, J., Raynaud, D., Barkov, N.I., Delaygue, G., Delmotte, M., Kotlyakov, V.M., Legrand, M., Lipenkov, V.Y., Lorius, C., Saltzman, E., 1999. Climate and atmospheric history of the past 420,000 years from the Vostok ice core, Antarctica 399, 8.
- Pollyea, R.M., Rimstidt, J.D., 2017. Rate equations for modeling carbon dioxide sequestration in basalt. Applied Geochemistry 81, 53–62. <https://doi.org/10.1016/j.apgeochem.2017.03.020>
- 1300 Rahman, S., Aller, R.C., Cochran, J.K., 2017. The Missing Silica Sink: Revisiting the Marine Sedimentary Si Cycle Using Cosmogenic ³² Si: The Missing Sedimentary Silica Sink. Global Biogeochem. Cycles 31, 1559–1578. <https://doi.org/10.1002/2017GB005746>
- Rau, G.H., 2011. CO₂ Mitigation via Capture and Chemical Conversion in Seawater. Environ. Sci. Technol. 45, 1088–1092. <https://doi.org/10.1021/es102671x>
- 1305 Rau, G.H., 2008. Electrochemical Splitting of Calcium Carbonate to Increase Solution Alkalinity: Implications for Mitigation of Carbon Dioxide and Ocean Acidity. Environ. Sci. Technol. 42, 8935–8940. <https://doi.org/10.1021/es800366q>
- Rau, G.H., Caldeira, K., 1999. Enhanced carbonate dissolution: a means of sequestering waste CO₂ as ocean bicarbonate. Energy Conversion 11.
- 1310 Rau, G.H., Carroll, S.A., Bourcier, W.L., Singleton, M.J., Smith, M.M., Aines, R.D., 2013. Direct electrolytic dissolution of silicate minerals for air CO₂ mitigation and carbon-negative H₂ production. Proc. Natl. Acad. Sci. U.S.A. 110, 10095–10100. <https://doi.org/10.1073/pnas.1222358110>
- Rau, G.H., Knauss, K.G., Langer, W.H., Caldeira, K., 2007. Reducing energy-related CO₂ emissions using accelerated weathering of limestone. Energy 32, 1471–1477. <https://doi.org/10.1016/j.energy.2006.10.011>
- 1315 Regnier, P., Friedlingstein, P., Ciais, P., Mackenzie, F.T., Gruber, N., Janssens, I.A., Laruelle, G.G., Lauerwald, R., Luyssaert, S., Andersson, A.J., Arndt, S., Arnosti, C., Borges, A.V., Dale, A.W., Gallego-Sala, A., Godd eris, Y., Goossens, N., Hartmann, J., Heinze, C., Ilyina, T., Joos, F., LaRowe, D.E., Leifeld, J., Meysman, F.J.R., Munhoven, G., Raymond, P.A., Spahni, R., Suntharalingam, P., Thullner, M., 2013. Anthropogenic perturbation of the carbon fluxes from land to ocean. Nature Geosci 6, 597–607. <https://doi.org/10.1038/ngeo1830>
- 1320 Renforth, P., Baltruschat, S., Peterson, K., Mihailova, B.D., Hartmann, J., 2022. Using ikaite and other hydrated carbonate minerals to increase ocean alkalinity for carbon dioxide removal and environmental remediation. Joule 6, 2674–2679. <https://doi.org/10.1016/j.joule.2022.11.001>
- Renforth, P., Campbell, J.S., 2021. The role of soils in the regulation of ocean acidification. Phil. Trans. R. Soc. B 376, 20200174. <https://doi.org/10.1098/rstb.2020.0174>
- 1325 Renforth, P., Henderson, G., 2017. Assessing ocean alkalinity for carbon sequestration: Ocean Alkalinity for C Sequestration. Rev. Geophys. 55, 636–674. <https://doi.org/10.1002/2016RG000533>

- Renforth, P., Jenkins, B.G., Kruger, T., 2013. Engineering challenges of ocean liming. *Energy* 60, 442–452. <https://doi.org/10.1016/j.energy.2013.08.006>
- 1330 Renforth, P., Kruger, T., 2013. Coupling Mineral Carbonation and Ocean Liming. *Energy Fuels* 27, 4199–4207. <https://doi.org/10.1021/ef302030w>
- Riebesell, U., Basso, D., Geilert, S., Dale, A. W., Kreuzburg, M., and Meysman, F.: Mesocosm experiments in ocean alkalinity enhancement research, *State Planet Discuss.* [preprint], <https://doi.org/10.5194/sp-2023-11>, in review, 2023.
- Rigopoulos, I., Harrison, A.L., Delimitis, A., Ioannou, I., Efstathiou, A.M., Kyratsi, T., Oelkers, E.H., 2018. Carbon sequestration via enhanced weathering of peridotites and basalts in seawater. *Applied Geochemistry* 91, 197–207. <https://doi.org/10.1016/j.apgeochem.2017.11.001>
- 1335 Rodriguez-Blanco, J.D., Shaw, S., Benning, L.G., 2011. The kinetics and mechanisms of amorphous calcium carbonate (ACC) crystallization to calcite, viavaterite. *Nanoscale* 3, 265–271. <https://doi.org/10.1039/CONR00589D>
- Sano, Y., Hao, Y., Kuwahara, F., 2018. Development of an electrolysis based system to continuously recover magnesium from seawater. *Heliyon* 4, e00923. <https://doi.org/10.1016/j.heliyon.2018.e00923>
- 1340 Sarmiento, J.L., Gruber, N., 2006. *Ocean Biogeochemical Dynamics*. Princeton University Press.
- Schuiling, R.D., De Boer, P.L., 2011. Rolling stones; fast weathering of olivine in shallow seas for cost-effective CO₂ capture and mitigation of global warming and ocean acidification (preprint). *Management of the Earth system: carbon sequestration and management*.
- Seeländer, K., 2023. *Alkalinity enhancement in rivers (Bachelor Thesis)*. University of Southern Denmark, Odense, DK.
- 1345 Shahar, A., Bassett, W.A., Mao, H.-K., Chou, I.-M., Mao, W., 2005. The stability and Raman spectra of ikaite, CaCO₃·6H₂O, at high pressure and temperature. *American Mineralogist* 90, 1835–1839. <https://doi.org/10.2138/am.2005.1783>
- Simkin, T., Smith, J.V., 1970. Minor-Element Distribution in Olivine. *The Journal of Geology* 78, 304–325. <https://doi.org/10.1086/627519>
- Smith, S.M., Geden, O., Nemet, G.F., Gidden, M.J., Lamb, W.F., Powis, C., Bellamy, R., Callaghan, M.W., Cowie, A., Cox, E., Fuss, S., Gasser, T., Grassi, G., Greene, J., Lück, S., Mohan, A., Müller-Hansen, F., Peters, G.P., Pratama, Y., Repke, T., Riahi, K., Schenuit, F., Steinhauser, J., Strefler, J., Valenzuela, J.M., Minx, J.C., 2023. The State of Carbon Dioxide Removal - 1st Edition. *The State of Carbon Dioxide Removal*. <https://doi.org/10.17605/OSF.IO/W3B4Z>
- 1350 Sommer, S., Gier, J., Treude, T., Lomnitz, U., Dengler, M., Cardich, J., Dale, A.W., 2016. Depletion of oxygen, nitrate and nitrite in the Peruvian oxygen minimum zone cause an imbalance of benthic nitrogen fluxes. *Deep Sea Research Part I: Oceanographic Research Papers* 112, 113–122. <https://doi.org/10.1016/j.dsr.2016.03.001>
- Sonnichsen, C., Atamanchuk, D., Hendricks, A., Morgan, S., Smith, J., Grundke, I., Luy, E., Sieben, V.J., 2023. An Automated Microfluidic Analyzer for In Situ Monitoring of Total Alkalinity. *ACS Sens.* 8, 344–352. <https://doi.org/10.1021/acssensors.2c02343>
- 1360 Stolaroff, J.K., Keith, D.W., Lowry, G.V., 2008. Carbon Dioxide Capture from Atmospheric Air Using Sodium Hydroxide Spray. *Environ. Sci. Technol.* 42, 2728–2735. <https://doi.org/10.1021/es702607w>

- Strathmann, H., Giorno, L., Drioli, E., 2011. An Introduction to Membrane Science and Technology.
- Strefler, J., Amann, T., Bauer, N., Krieglner, E., Hartmann, J., 2018. Potential and costs of carbon dioxide removal by enhanced weathering of rocks. *Environ. Res. Lett.* 13, 034010. <https://doi.org/10.1088/1748-9326/aaa9c4>
- 1365 Sun, X., Turchyn, A.V., 2014. Significant contribution of authigenic carbonate to marine carbon burial. *Nature Geosci* 7, 201–204. <https://doi.org/10.1038/ngeo2070>
- Talabi, O.O., Dorfi, A.E., O’Neil, G.D., Esposito, D.V., 2017. Membraneless electrolyzers for the simultaneous production of acid and base. *Chem. Commun.* 53, 8006–8009. <https://doi.org/10.1039/C7CC02361H>
- Terlouw, T., Bauer, C., Rosa, L., Mazzotti, M., 2021. Life cycle assessment of carbon dioxide removal technologies: a critical review. *Energy Environ. Sci.* 14, 1701–1721. <https://doi.org/10.1039/D0EE03757E>
- 1370 Thomsen, J.K., Geest, T., Cox, R.P., 1994. Mass Spectrometric Studies of the Effect of pH on the Accumulation of Intermediates in Denitrification by *Paracoccus denitrificans*. *Appl Environ Microbiol* 60, 536–541. <https://doi.org/10.1128/aem.60.2.536-541.1994>
- Torres, M.E., Hong, W.-L., Solomon, E.A., Milliken, K., Kim, J.-H., Sample, J.C., Teichert, B.M.A., Wallmann, K., 2020. Silicate weathering in anoxic marine sediment as a requirement for authigenic carbonate burial. *Earth-Science Reviews* 200, 102960. <https://doi.org/10.1016/j.earscirev.2019.102960>
- 1375 Tréguer, P.J., Sutton, J.N., Brzezinski, M., Charette, M.A., Devries, T., Dutkiewicz, S., Ehlert, C., Hawkins, J., Leynaert, A., Liu, S.M., Llopi Monferrer, N., López-Acosta, M., Maldonado, M., Rahman, S., Ran, L., Rouxel, O., 2021. Reviews and syntheses: The biogeochemical cycle of silicon in the modern ocean. *Biogeosciences* 18, 1269–1289. <https://doi.org/10.5194/bg-18-1269-2021>
- 1380 Tyka, M.D., Van Arsdale, C., Platt, J.C., 2022. CO₂ capture by pumping surface acidity to the deep ocean. *Energy Environ. Sci.* 15, 786–798. <https://doi.org/10.1039/D1EE01532J>
- Volkenborn, N., Robertson, D.M., Reise, K., 2009. Sediment destabilizing and stabilizing bio-engineers on tidal flats: cascading effects of experimental exclusion. *Helgol Mar Res* 63, 27–35. <https://doi.org/10.1007/s10152-008-0140-9>
- Wallmann, K., Aloisi, G., Haeckel, M., Tishchenko, P., Pavlova, G., Greinert, J., Kutterolf, S., Eisenhauer, A., 2008. Silicate weathering in anoxic marine sediments. *Geochimica et Cosmochimica Acta* 72, 2895–2918. <https://doi.org/10.1016/j.gca.2008.03.026>
- 1385 Wallmann, K., Diesing, M., Scholz, F., Rehder, G., Dale, A.W., Fuhr, M., Suess, E., 2022. Erosion of carbonate-bearing sedimentary rocks may close the alkalinity budget of the Baltic Sea and support atmospheric CO₂ uptake in coastal seas. *Front. Mar. Sci.* 9, 968069. <https://doi.org/10.3389/fmars.2022.968069>
- 1390 Wang, H., Pilcher, D.J., Kearney, K.A., Cross, J.N., Shugart, O.M., Eisaman, M.D., Carter, B.R., 2023. Simulated Impact of Ocean Alkalinity Enhancement on Atmospheric CO₂ Removal in the Bering Sea. *Earth’s Future* 11. <https://doi.org/10.1029/2022EF002816>

- Willauer, H.D., DiMascio, F., Hardy, D.R., Williams, F.W., 2014. Feasibility of CO₂ Extraction from Seawater and Simultaneous Hydrogen Gas Generation Using a Novel and Robust Electrolytic Cation Exchange Module Based on Continuous Electrodeionization Technology. *Ind. Eng. Chem. Res.* 53, 12192–12200. <https://doi.org/10.1021/ie502128x>
- 1395
- Yakymchko, Y., Lutsyuk, I., Jaskulski, R., Dulnik, J., Kropyvnytska, T., 2020. The Effect of Vibro-Activation Time on the Properties of Highly Active Calcium Hydroxide. *Buildings* 10. <https://doi.org/10.3390/buildings10060111>
- Zarandi, A.E., Larachi, F., Beaudoin, G., Plante, B., Sciortino, M., 2017. Ambient mineral carbonation of different lithologies of mafic to ultramafic mining wastes/tailings – A comparative study. *International Journal of Greenhouse Gas Control* 63, 392–400. <https://doi.org/10.1016/j.ijggc.2017.06.016>
- 1400